

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2013-001-I	COOK	17	5

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
5713 South McVicker Avenue	0.0	0.0	0.0	18.0	60.0	0.0	0.0	0.0	0.0	Replace broken courtesy walk and 2 sidewalk squares (tripping hazard)
5732 South McVicker Avenue	0.0	0.0	0.0	18.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares and 12 ft of Service Walk
5844 South McVicker Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
5923 South McVicker Avenue	8.0	1.4	0.0	12.0	0.0	0.0	0.0	0.0	0.0	Replace 8 Feet of New Curb In Front of House
6010 South McVicker Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (tripping hazard)
6240 South McVicker Avenue	0.0	0.0	0.0	15.0	0.0	0.0	0.0	0.0	0.0	Replace 10 ft of Courtesy Walk
5716 South Meade Avenue	0.0	0.0	0.0	25.5	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares and New Courtesy Walk
5804 South Meade Avenue	0.0	0.0	0.0	13.5	0.0	0.0	0.0	0.0	0.0	Replace hazardous service walk
5842 South Meade Avenue	0.0	0.0	0.0	22.5	30.0	0.0	0.0	0.0	0.0	Replace 15 ft of Carriage Walk. Also Replace Sidewalk Square Near Alley (Tripping Hazard)
6036 South Meade Avenue	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	Install 20 Feet of curb in front of house. (ponding water)
6052 South Meade Avenue	8.0	1.4	0.7	6.0	0.0	0.0	0.0	0.0	0.0	Replace 8 ft of broken curb and part of sidewalk
5644 South Melvina Avenue	10.0	1.7	1.4	3.0	0.0	0.0	0.0	0.0	0.0	Replace 10 feet of damaged curb and gutter
6113 South Melvina Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6135 South Menard Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares
5625 South Merrimac Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares
5643 South Merrimac Avenue	0.0	0.0	0.0	15.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares & 10 ft of courtesy walk.
5653 South Merrimac Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 Sidewalk Squares
6035 - 6037 South Merrimac Avenue	50.0	8.4	7.7	6.0	0.0	0.0	0.0	0.0	0.0	Replace 50 Feet of New Curb & Gutter from 6035 to 6037 Merrimac Avenue
6055 South Merrimac Avenue	3.0	0.5	0.0	4.5	0.0	0.0	0.0	0.0	0.0	Replace 3 Feet of Curb
5517 South Mobile Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6000 South Mobile Avenue	0.0	0.0	0.0	0.0	0.0	0.0	350.0	20.0	30.0	Replace ADA Ramp & Alley Apron in Concrete
5514 South Moody Avenue	20.0	3.4	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace alley apron with concrete
5515 South Moody Avenue	20.0	3.4	0.0	0.0	30.0	0.0	350.0	0.0	30.0	Replace alley apron with concrete and 1 chipped sidewalk square.
5521 South Moody Avenue	15.0	2.5	0.0	22.5	0.0	0.0	0.0	0.0	0.0	Replace 15 ft of curb.
5658 South Moody Avenue	0.0	0.0	0.0	9.0	240.0	0.0	0.0	0.0	0.0	Replace 7 Sidewalk Squares and courtesy walk on side of house (on 57th St). Also replace 1 sidewalk square in front of house.
SUB-TOTAL	134.0	22.7	9.8	190.5	1320.0	0.0	1050.0	20.0	110.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES