



CONSTRUCTION SEQUENCING

THE CONTRACTOR SHALL FIRST INSTALL THE INFLATABLE BLADDER BULKHEAD (BULKHEAD TUNNEL, SPECIAL) AT LOCATION A THEN FOLLOWED BY INSTALLATION OF THE INFLATABLE BLADDER BULKHEAD AT LOCATION B.

THE DURATION BETWEEN INSTALLATION OF THE BULKHEADS AT LOCATION A AND LOCATION B MAY NOT EXCEED 1 WEEK (7 CAL DAYS).

WORK SHALL THEN PROCEED BY FILLING THE GATE SHAFT NO. 2, FILLING OF THE TUNNEL ALONG HARRISON, THEN FILLING OF THE TUNNELS ALONG HALSTED AND VAN BUREN. THE CONTRACTOR SHALL NOT DEVIATE FROM THIS CONSTRUCTION SEQUENCE, UNLESS OTHERWISE APPROVED BY THE ENGINEER.

LEGEND

- ▣ FILL WITH CLSM, SPECIAL
- ▣ PROPOSED BULKHEAD TUNNEL
- ▣ PROPOSED BULKHEAD TUNNEL, SPECIAL
- ▣ EXISTING BULKHEAD
- ⊙ SOIL BORING LOCATION
- x SPOT ELEVATION

FILE NAME: 1-FILES

COLLINS ENGINEERS

USER NAME: <i>mromper</i>	DESIGNED: -	REVISED: -	5/30/2013 R.A.G.
PLOT SCALE: 1/8" = 100.0000' / 1" = 1000.0000'	DRAWN: -	REVISED: -	
PLOT DATE: 7/10/2013	CHECKED: -	REVISED: -	
	DATE: -	REVISED: -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

OVERALL BULKHEAD AND
CONCRETE FILL PLAN

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

P.A.I. RTE. 90/94	SECTION 0101.6-2P-1-3 (13)	COUNTY COOK	TOTAL SHEETS 37	SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W36	

REV. 7-9-13