ROUTE: EB IL 56 (IL 53 to Gray Ave.)

| CROSS STREET FROM | CROSS STREET TO | DIRECTION (EB/WB) (NB/SB) | LANE NO. (1, 2, 3) | PAVEMENT PATCH WIDTH | PAVEMENT PATCH LENGTH | REPAIR AREA (SQ FT) | REPAIR AREA (SQ YD) |
|---|---|---|---|---|---|---|---|
| IL 53 | | EB | 1 | 12 | 6 | 72 | 8 |
| | | EB | 1 | 12 | 6 | 72 | 8 |
| | | EB | 1 | 12 | 15 | 180 | 20 |
| | | EB | 1 | 12 | 8 | 96 | 11 |
| | | EB | 1 | 12 | 6 | 72 | 8 |
| | | EB | 2 | 12 | 6 | 72 | 8 |
| | | EB | 2 | 12 | 8 | 96 | 11 |
| | | EB | 2 | 12 | 8 | 96 | 11 |
| | | EB | 2 | 12 | 10 | 120 | 13 |
| | | EB | 2 | 12 | 10 | 120 | 13 |
| | | EB | 2 | 12 | 10 | 120 | 13 |
| | | EB | 2 | 12 | 6 | 72 | 8 |
| | | EB | 1&2 | 3 | 50 | 150 | 17 |
| | | EB | 1&2 | 3 | 50 | 150 | 17 |
| | | EB | 1&2 | 3 | 50 | 150 | 17 |
| | | EB | 1&2 | 3 | 100 | 300 | 33 |
| | | EB | 3 | 12 | 6 | 72 | 8 |
| | | EB | 3 | 12 | 6 | 72 | 8 |
| | | EB | 3 | 12 | 25 | 300 | 33 |
| | | EB | 2&3 | 12 | 200 | 2400 | 267 |
| | Gray Ave | EB | 2&3 | 3 | 100 | 300 | 33 |
| | | | | | | | |
| | | **TOTALS:** | | | **686** | | **565** |
| | | | | | **FT** | | **SY** |

ROUTE: EB IL 56 (Woodcreek Dr. to Esplanade Dr.)

| CROSS STREET FROM | CROSS STREET TO | DIRECTION (EB/WB) (NB/SB) | LANE NO. (1, 2, 3) | PAVEMENT PATCH WIDTH | PAVEMENT PATCH LENGTH | REPAIR AREA (SQ FT) | REPAIR AREA (SQ YD) |
|---|---|---|---|---|---|---|---|
| | | | | | | | |
| Woodcreek Dr | Esplanade Dr | EB | 1&2 | 3 | 400 | 1200 | 133 |
| | | | | | | | |
| | | **TOTALS:** | | | **400** | | **133** |
| | | | | | **FT** | | **SY** |

ROUTE: EB IL 56 (W/O Fairfield Ave. to Trans Am Plaza Dr.)

| CROSS STREET FROM | CROSS STREET TO | DIRECTION (EB/WB) (NB/SB) | LANE NO. (1, 2, 3) | PAVEMENT PATCH WIDTH | PAVEMENT PATCH LENGTH | REPAIR AREA (SQ FT) | REPAIR AREA (SQ YD) |
|---|---|---|---|---|---|---|---|
| W/O Fairfield Ave | | EB | 1 | 12 | 6 | 72 | 8 |
| | | EB | 1 | 12 | 6 | 72 | 8 |
| | | EB | 1 | 12 | 6 | 72 | 8 |
|