SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4					
40600300	AGGREGATE (PRIME COAT)	TON	16	16					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	229	229					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	854	854					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	7625	7625					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	270	270					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	90	90					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	612	612					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2732	2732					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	234	234					

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	800	800					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	135	135					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	135	135					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	240	240					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	514	514					

* SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\tarlofm\d0335f18\viewl-COOK-CENTRAL-Design.dgn	USER NAME = tarlofm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2013-033 RS	COOK	21	3

CONTRACT NO. 60W69

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT