

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	GRAND TOTAL	0021 90% FED 10% STATE <i>HSIP</i> TOTAL QUANTITY	0005 80% FED 20% STATE <i>F</i> TOTAL QUANTITY
54001011	BOX CULVERT END SECTIONS, CULVERT NO. 11	EACH	1	1	
54001012	BOX CULVERT END SECTIONS, CULVERT NO. 12	EACH	1	1	
54001013	BOX CULVERT END SECTIONS, CULVERT NO. 13	EACH	1	1	
54001014	BOX CULVERT END SECTIONS, CULVERT NO. 14	EACH	1	1	
54001015	BOX CULVERT END SECTIONS, CULVERT NO. 15	EACH	1	1	
54001016	BOX CULVERT END SECTIONS, CULVERT NO. 16	EACH	1	1	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	20	20	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	6	6	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	126	126	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	2025	2025	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	302	302	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	183	183	
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	452	452	
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	188	188	
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	130	130	
542D5497	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	142	142	
542D8227	PIPE CULVERTS, CLASS D, TYPE 2 EQUIVALENT ROUND-SIZE 42"	FOOT	54	54	
54213447	END SECTIONS 12"	EACH	5	5	
54213450	END SECTIONS 15"	EACH	94	94	
54213453	END SECTIONS 18"	EACH	9	9	
54213459	END SECTIONS 24"	EACH	9	9	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	4	4	
54248510	CONCRETE COLLAR	CU YD	0.3	0.3	

*h* • SPECIALTY ITEMS

FILE NAME *	USER NAME * grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 599	SECTION (83MFT & 103MFT)W	COUNTY ROCK ISLAND	TOTAL SHEETS 340	SHEET NO. 6
Default	11-shc-schedule.dgn	DRAWN -	REVISED -							
	PLOT SCALE * 100.0000 "/> <td>CHECKED -</td> <td>REVISED -</td> <td></td> <td>SCALE:</td> <td>SHEET</td> <td>OF</td> <td>SHEETS</td> <td>STA.</td> <td>TO STA.</td>	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE * Wed Mar 20 10:55:33 2013	DATE -	REVISED -							
										ILLINOIS FED. AID PROJECT CONTRACT NO. 64H11