

SCHEDULE OF QUANTITIES

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	REMARKS
719.0	Sta. 802+15.0 TO 1017+84.0	Yellow CL, 1 lift
55.7	LT Sta. 805+93.0 TO 822+63.0	White Edge, Guardrail Section, 1 lift
11.5	LT Sta. 831+29.0 TO 834+74.0	White Edge, Guardrail Section, 1 lift
9.9	LT Sta. 842+97.0 TO 845+94.0	White Edge, Guardrail Section, 1 lift
11.5	LT Sta. 855+52.0 TO 858+98.0	White Edge, Guardrail Section, 1 lift
10.3	LT Sta. 864+86.0 TO 867+94.0	White Edge, Guardrail Section, 1 lift
9.4	LT Sta. 868+78.0 TO 871+60.0	White Edge, Guardrail Section, 1 lift
8.1	LT Sta. 899+13.0 TO 901+57.0	White Edge, Guardrail Section, 1 lift
11.5	LT Sta. 916+19.0 TO 919+64.0	White Edge, Guardrail Section, 1 lift
11.5	RT Sta. 916+19.0 TO 919+64.0	White Edge, Guardrail Section, 1 lift
8.7	RT Sta. 948+84.0 TO 951+45.0	White Edge, Guardrail Section, 1 lift
7.1	LT Sta. 949+33.0 TO 951+45.0	White Edge, Guardrail Section, 1 lift
4.9	RT Sta. 952+43.0 TO 953+91.0	White Edge, Guardrail Section, 1 lift
8.1	LT Sta. 952+43.0 TO 954+85.0	White Edge, Guardrail Section, 1 lift
887.1	TOTAL	

78001110 PAINT PAVEMENT MARKING - LINE 4"

2 Coats

FOOT	LOCATION	REMARKS
567.5	Sta. 802+15.0 TO 806+69.0	Yellow - LT Skip, RT Solid
350.8	Sta. 806+69.0 TO 820+72.0	Yellow - CL Skip
1182.5	Sta. 820+72.0 TO 830+18.0	Yellow - LT Solid, RT Skip
2385.5	Sta. 830+18.0 TO 925+60.0	Yellow - CL Skip
745.0	Sta. 925+60.0 TO 931+56.0	Yellow - LT Skip, RT Solid
961.3	Sta. 931+56.0 TO 939+25.0	Yellow - LT Solid, RT Skip
1983.5	Sta. 939+25.0 TO 1018+59.0	Yellow - CL Skip
	16352.0 YELLOW TOTAL	
	103884.0 GRAND TOTAL	

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	REMARKS
272	Sta. 802+15.0 TO 1018+59.0	Along CL
272	TOTAL	

78001110 PAINT PAVEMENT MARKING - LINE 4"

2 Coats

ONE COAT	TWO COATS	LOCATION	REMARKS
18978.0	37956.0	LT Sta. 802+15.0 TO 991+93.0	1 White Solid Edge Line - to 121st St
537.0	1074.0	LT Sta. 992+91.0 TO 998+28.0	1 White Solid Edge Line - to 120th St
843.0	1686.0	LT Sta. 999+31.0 TO 1007+74.0	1 White Solid Edge Line - New Sideroad
769.0	1538.0	LT Sta. 1009+08.0 TO 1016+77.0	1 White Solid Edge Line - 7th St
101.0	202.0	LT Sta. 1017+58.0 TO 1018+59.0	1 White Solid Edge Line - to 120th St
6628.0	13256.0	RT Sta. 802+15.0 TO 868+43.0	1 White Solid Edge Line - to 154th St
3204.0	6408.0	RT Sta. 869+66.0 TO 901+70.0	1 White Solid Edge Line - to 147th St
1869.0	3738.0	RT Sta. 902+82.0 TO 921+51.0	1 White Solid Edge Line - to 144th St
2477.0	4954.0	RT Sta. 922+53.0 TO 947+30.0	1 White Solid Edge Line - to 140th St
2450.0	4900.0	RT Sta. 948+45.0 TO 972+95.0	1 White Solid Edge Line - to 126th St
3116.0	6232.0	RT Sta. 973+97.0 TO 1005+13.0	1 White Solid Edge Line - to Timber Ridge Dr
1249.0	2498.0	RT Sta. 1006+10.0 TO 1018+59.0	1 White Solid Edge Line - to end of job
141.0	282.0	154th St W - South Side	White Solid Edge Lines
195.0	390.0	147th St W - South Side	White Solid Edge Lines
231.0	462.0	144th St W - South Side	White Solid Edge Lines
180.0	360.0	140th St W - South Side	White Solid Edge Lines
129.0	258.0	126th St W - South Side	White Solid Edge Lines
126.0	252.0	121st St - North Side	White Solid Edge Lines
234.0	468.0	120th St - North Side	White Solid Edge Lines
110.0	220.0	Timber Ridge Dr - South Side	
104.0	208.0	New Sideroad - North Side	
95.0	190.0	7th St W - North Side	
87532.0	WHITE TOTAL		

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	REMARKS
8	LT Sta. 806+27.3 TO 822+27.3	80' spacing for first 400', then 400' spacing after
4	LT Sta. 831+63.3 TO 834+38.3	80' spacing
3	LT Sta. 843+32.3 TO 845+57.3	80' spacing
4	LT Sta. 855+87.3 TO 858+62.3	80' spacing
3	LT Sta. 865+21.0 TO 867+58.5	80' spacing
3	LT Sta. 869+12.5 TO 871+25.0	80' spacing
3	LT Sta. 899+47.5 TO 901+22.5	80' spacing
4	LT Sta. 916+54.5 TO 919+29.5	80' spacing
4	RT Sta. 916+54.5 TO 919+29.5	80' spacing
36	TOTAL	