

HOT-MIX ASPHALT SCHEDULE

STATIONING		REMARKS	H.M.A.		H.M.A. AREA SQ. YD.	X4060110	40600982	40600985	40600990	40600627	40603310
			LENGTH FEET	WIDTH FEET		* BIT PRIME (2 COATS) POUND	* H.M.A. SURF REM BUTT JOINT SQ. YD.	* P.C.C. SURF REM BUTT JOINT SQ. YD.	* TEMP. RAMP SQ. YD.	LEVEL BINDER (MM) IL 9.5FG, N50 TON	H.M.A. SURF. CSE. MIX "C", N50 TON
IL 92 - SHOULDERS											
<i>LEFT</i>											
802+90.0	- 805+93.0		303	3	101	115.54					14.1
805+93.0	- 822+63.0	To post of GR	1670	4.5	835	955.24					116.9
822+63.0	- 831+28.0		865	3	288	329.85					40.4
831+28.0	- 834+74.0	To post of GR	346	4.5	173	197.91					24.2
834+74.0	- 842+97.0		823	3	274	313.84					38.4
842+97.0	- 845+94.0	To post of GR	297	4.5	149	169.88					20.8
845+94.0	- 855+52.0		958	3	319	365.32					44.7
855+52.0	- 858+98.0	To post of GR	346	4.5	173	197.91					24.2
858+98.0	- 864+86.0		588	3	196	224.22					27.4
864+86.0	- 867+94.0	To post of GR	308	4.5	154	176.18					21.6
867+94.0	- 868+77.0		83	3	28	31.65					3.9
868+77.0	- 871+61.0	To post of GR	284	4.5	142	162.45					19.9
871+61.0	- 899+12.0		2751	3	917	1049.05					128.4
899+12.0	- 901+57.0	To post of GR	245	4.5	123	140.14					17.2
901+57.0	- 916+19.0		1462	3	487	557.51					68.2
916+19.0	- 919+65.0	To post of GR	346	4.5	173	197.91					24.2
919+65.0	- 945+68.0		2603	3	868	992.61					121.5
945+68.0	- 949+44.0	Contract #64D18 Widening	376	VAR	413	472.98					57.9
949+44.0	- 951+65.0	To post of GR	221	7	172	196.64					24.1
951+65.0	- 952+43.0	Omission - Bridge	78								
952+43.0	- 954+85.0	To post of GR	242	7	188	215.33					26.4
954+85.0	- 991+93.0		3708	3	1236	1413.98					173.0
991+93.0	- 992+92.0	Omission - 121st Street W	99								
992+92.0	- 995+64.0		272	3	91	103.72					12.7
995+64.0	- 997+03.0	Omission - New Concrete/HMA	139								
997+03.0	- 998+28.0	To post of GR	125	8.5	118	135.06					16.5
998+28.0	- 999+30.0	Omission - 120th Street W	102								
999+30.0	- 1007+73.0		843	3	281	321.46					39.3
1007+73.0	- 1009+07.0	Omission - New Sideroad	134								
1009+07.0	- 1016+77.0		770	3	257	293.63					35.9
1016+77.0	- 1017+58.0	Omission - 7th Street W	81								
1017+58.0	- 1017+84.0		26	3	9	9.91					1.2

* ADDITIONAL QUANTITIES ON ENTRANCE SCHEDULE

FILE NAME *	USER NAME * grenton	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HOT-MIX ASPHALT SCHEDULE	F.A.P. RTE. 599	SECTION (83MFT & 103MFT)W	COUNTY ROCK ISLAND	TOTAL SHEETS 340	SHEET NO. 37	
ci:\pw\work\pmdot\grenton\0261271\0207	11-sh1-schedule.dgn	DRAWN -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
Default	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -			CONTRACT NO. 64H11					
	PLOT DATE * Wed May 22 08:21:36 2013	DATE -	REVISED -			[ILLINOIS] FED. AID PROJECT					