

# EARTHWORK SCHEDULE

EARTH WORK SCHEDULE FOR CHANNEL EX. AT STA. 917+92.06 RT				
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
1+10 - 1+80	655	491	190	301
<b>TOTAL</b>	655	491	190	301

C64H11 EARTH WORK SCHEDULE STA. 975+67 LT				
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
5+30 - 6+ 20	167	125	228	-103
<b>TOTAL</b>	167	125	228	-103