LUND HOLGER W | KENSINGER MICHAEL J | DOOLEY LARRY R | ALLISON DANIEL | PETERSON WILLIAM E | SIMS DAVID

N

PE +35

STA. 964+82 52' LT
36' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

PE +82

EXISTING R.O.W.

PE +94

STA. 966+94 47' LT
34' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

CONSTRUCTION LIMITS

CONSTRUCTION LIMITS

Match Line Sta. 963+00.00

Match Line Sta. 969+00.00

12' 9' 15' 13'

3' 13' 13' 3'

963 964 965+00 966 967 968

IL 92

15" CMP

17'

PE +97

STA. 963+97 26' RT
54' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

CONSTRUCTION LIMITS

PROPOSED R.O.W.

EXISTING R.O.W.

963+50.00
55.00 RT

PE +76

PE +32

PE +33

FE +17

STA. 966+00 28' RT
100' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

STA. 967+33 28' RT
38' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

STA. 968+17 29' RT
60' P CUL. CL D. T1. 15"
2 EA. END SECTIONS. 15"

FENCHEL BRADLEY/WOOLEY R | KRUEGER MICHAEL L | LEONARD TIMOTHY A | DONNELLY JUDY C | LARSON WAYNE K

PLAN
DATE
BY
SURVEYED
PLOTTED
GRADES CHECKED
ALIGNMENTS CHECKED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
C400 FILE NAME

PROFILE
DATE
BY
SURVEYED
PLOTTED
GRADES CHECKED
ALIGNMENTS CHECKED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.

LEGEND

=TREE REMOVAL ACRES

X = TREE REMOVAL

= DRIVEWAY PAVEMENT REMOVAL

= PAVEMENT REMOVAL

595 590 585 580 575 570 565 560 555

569.99 +1.10% 570.64 +1.28% 571.18 +1.88% 574.00 +1.88% 574.50 +0.50% 575.00 +1.00% 575.50 +0.50% 577.00 +3.00%

SPECIAL DITCH RT

SPECIAL DITCH RT

STA. 963+00 to 969+00
EARTH EX. = 935.4 CU.YDS.
EMB. = 289.9 CU.YDS.
WASTE = 411.6 CU.YDS.

963+00	963+50	964+00	964+50	965+00	965+50	966+00	966+50	967+00	967+50	968+00	968+50	969+00
572.22 / 572.43	572.51 / 572.72	572.80 / 573.01	573.10 / 573.30	573.41 / 573.62	573.73 / 573.94	574.05 / 574.26	574.37 / 574.58	574.68 / 574.89	574.99 / 575.20	575.30 / 575.51	575.59 / 575.80	575.88 / 576.09	576.17 / 576.38	576.48 / 576.69	576.82 / 577.03	577.17 / 577.37	577.50 / 577.71	577.81 / 578.02	578.12 / 578.33	578.41 / 578.62	578.66 / 578.86	578.90 / 579.11	579.14 / 579.35	579.32 / 579.53

FILE NAME = c:\pw_work\pwidot\grantpm\d0261271\D207411-sht-plnpro.dgn	USER NAME = grantpm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 41.5770 ' / in.	CHECKED -	REVISED -
	PLOT DATE = Wed Mar 20 11:26:24 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 92 Plan & Profile

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	(83MFT & 103MFT)W	ROCK ISLAND	340	78
		CONTRACT NO. 64H11		
		ILLINOIS	FED. AID PROJECT	