

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				Roadway	Structure	Brimfield	Safety	state
				0005 80% - 20%	0040 80% - 20%	0005 100%	0021 80% - 20%	0005 100%
20100500	TREE REMOVAL, ACRES	ACRE	0.32	0.32				
20200100	EARTH EXCAVATION	CU YD	1450	1450				
20200500	EARTH EXCAVATION (WIDENING)	CU YD	220				220	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	108		108			
20400800	FURNISHED EXCAVATION	CU YD	67	67				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	418		418			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	72		72			
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	1569	1569				
* 25000305	SEEDING, CLASS 3A	ACRE	0.32	0.32				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	29	29				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	29	29				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	29	29				
* 25100115	MULCH, METHOD 2	ACRE	0.19	0.19				
25100630	EROSION CONTROL BLANKET	SQ YD	651	651				

\*SPECIALTY ITEM

14

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A. RTE. FAS 2402 U.S. 150	SECTION 010,111,112,113IRS-3; 114RS-4112C-2	COUNTY PEORIA	TOTAL SHEETS 76	SHEET NO. 7
FED AID PROJECT			CONTRACT NO. 68614	