

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				Roadway	Structure	Brimfield	Safety	state
				0005 80% - 20%	0040 80% - 20%	0005 100%	0021 80% - 20%	0005 100%
50800105	REINFORCEMENT BARS	POUND	24813	983	23830			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2770		2770			
51500100	NAME PLATES	EACH	1		1			
54003000	CONCRETE BOX CULVERTS	CU YD	166.5	10.5	156			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	65	65				
60602500	CONCRETE GUTTER, TYPE A	FOOT	300	300				
60603800	COMB. CONC. CURB AND GUTTER, TYPE B-6.12	FOOT	840			840		
60618760	CONCRETE MEDIAN, TYPE M-4.12	SO FT	258	258				
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SO FT	444	444				
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SO FT	1101	1101				
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	525	525				
* 63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	812.5	812.5				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	31	31				
63200310	GUARDRAIL REMOVAL	FOOT	1166	1166				

*SPECIALTY ITEM

14

DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN -	REVISED -			FAS 2402	(110,111,112,113)RS-3;			
CHECKED -	REVISED -			U.S. 150	114RS-4;112C-2	CONTRACT NO. 68614		
DATE -	REVISED -			FED AID PROJECT				