

SCHEDULE OF QUANTITIES

PAVEMENT GROOVING

	STATION	METRIC STATION (FOR INFORMATION ONLY)	WIDTH AT LOCATION	TO	STATION	METRIC STATION (FOR INFORMATION ONLY)	WIDTH AT LOCATION	NUMBER OF LANES	LENGTH (FOOT)	WIDTH (FEET)	AREA (SQ YD)	PAVEMENT GROOVING Z0037300 (SQ YD)
SOUTHBOUND												
	SB	283+25.53	34+909.000		303+21.90	34+300.506	40.0	3	1,996.37	37.0	8,207.3	8,207.3
	SB	303+21.90	34+300.506		308+51.10	34+139.208	48.0	4	529.20	48.0	2,822.4	2,822.4
	OMISSION	308+51.10	34+139.208		313+00.00		48.0		448.90			0.0
	STA EQ	313+00.00			312+10.37		BK					
	OMISSION	312+10.37			320+24.41	33+754.264	48.0		814.04			0.0
	OMISSION	320+24.41	33+754.264		325+65.73	33+589.268	48.0		541.32			0.0
	SB	325+65.73	33+589.268		378+82.23	31+968.800	36.0	3	5,316.50	33.0	19,493.8	19,493.8
SN 057-0234	OMISSION	378+82.23	31+968.800		382+88.07	31+845.100	36.0		405.84			0.0
	SB	382+88.07	31+845.100		398+42.20	31+371.400	36.0	3	1,554.13	33.0	5,698.5	5,698.5
NORTHBOUND												
	NB	320+38.40	33+750.000		378+82.23	31+968.800	36.0	3	5,843.83	33.0	21,427.4	21,427.4
SN 057-0233	OMISSION	378+82.23	31+968.800		382+88.07	31+845.100	36.0		405.84			0.0
	NB	382+88.07	31+845.100		398+42.20	31+371.400	36.0	3	1,554.13	33.0	5,698.5	5,698.5
	OMISSION	398+42.20			555+00.00		VAR		15,657.80			0.0
	NB	555+00.00			566+69.00		36.0	3	1,169.00	33.0	4,286.3	4,286.3
SN 057-0010	OMISSION	566+69.00			570+72.00		36.0		403.00			0.0
	NB	570+72.00			590+62.74		36.0	3	1,990.74	33.0	7,299.4	7,299.4
	NB	590+62.74			590+91.33		36.6	3	28.59	33.3	105.7	105.7
SN 057-0007	OMISSION	590+91.33			595+77.35		46.3		486.02			0.0
	NB	595+77.35			596+62.74		48.0	4	85.39	43.1	409.4	409.4
	NB	596+62.74			606+79.00		48.0	4	1,016.26	44.0	4,968.4	4,968.4
											TOTAL	80,417.1
											ROUNDED	80,500.0

CHANGEABLE MESSAGE SIGN

CHANGEABLE MESSAGE SIGN X7015005	
LOCATION	(CALENDAR DAYS)
I-55 NB	7
I-74 WB	7
I-55 SB	7
I-74 EB	7
*	15
*	15
TOTAL	58

*LOCATIONS TO BE DETERMINED BY ENGINEER

• F.A.I. 55, F.A.I. 74, & U.S. 51

FILE NAME =	USER NAME = bergana.j	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\p\idot\bergana.j\d0337583\0570A25-sh1-Schedule.dgn	PLA25-sh1-Schedule.dgn	DRAWN -	REVISED -			•	HSIP 2013-1	MCLEAN	11	10	
\$MODELNAME\$	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 70A25					
	PLOT DATE = 4/23/2013	DATE -	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	