

140

# SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 0004	BRIDGE 0011
				F. A. U. 7706	SN 054-0512
20100500	TREE REMOVAL, ACRES	ACRE	6.25	6.25	
20200100	EARTH EXCAVATION	CU YD	23685	23685	
20800150	TRENCH BACKFILL	CU YD	1260	1260	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	6815	6815	
* 25000200	SEEDING, CLASS 2	ACRE	13.5	13.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1221	1221	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1221	1221	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1221	1221	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	27	27	
25100115	MULCH, METHOD 2	ACRE	25.75	25.75	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	6255	6255	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	16	16	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1350	1350	
28000400	PERIMETER EROSION BARRIER	FOOT	5986	5986	

\* SPECIALTY ITEM

LAST SAVED : 5/23/2013  
 PEN TABLE : 18-Half.tbl  
 PLOT DRIVER : TR-V8ocf-BIack-Half.plt

FILE NAME : J:\06103\Cad\TX_Plans\003_0672789-Sht-5.dgn	USER NAME : jepettibone	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 40.0000 / IN.	CHECKED -	REVISED -	REVISED -					7706	23(B-1)	LOGAN	179	4
PLOT DATE : 5/23/2013 4:31:30 PM	DATE -	REVISED -	REVISED -		BUS. LOOP 55 OVER SALT CREEK			CONTRACT NO. 72789				
					SCALE: NONE	SHEET NO. 1 OF 10 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			