

URBAN

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 0004	BRIDGE 0011
				<del>0004</del>	<del>0011</del>
				F. A. U. 7706	SN 054-0512
5210030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	48		48
52100530	ANCHOR BOLTS, 1 1/4"	EACH	96		96
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2	
54215547	METAL END SECTIONS 12"	EACH	3	3	
54215559	METAL END SECTIONS 24"	EACH	3	3	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	30	30	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	130	130	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	50	50	
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	12	12	
55100300	STORM SEWER REMOVAL 8"	FOOT	70	70	
55100500	STORM SEWER REMOVAL 12"	FOOT	701	701	
55100700	STORM SEWER REMOVAL 15"	FOOT	700	700	

\* SPECIALTY ITEM

LAST SAVED: 5/23/2013 4:31:32 PM  
 PEN TABLE: VB-HAF-HI  
 PLOT DRIVER: TR-YEDef-Black-NoPlot

FILE NAME: \\06103\Cad\TS_Plans\003_0672789-Sht-5.dgn	USER NAME: jepettibone	DESIGNED: -	REVISED: -
PLOT SCALE: 48.0000' / IN.	CHECKED: -	DRAWN: -	REVISED: -
PLOT DATE: 5/23/2013 4:31:32 PM	DATE: -	REVISIONS: -	REVISIONS: -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE      SHEET NO. 6 OF 10 SHEETS      STA.      TO STA.

F. A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7706	23(B-D)	LOGAN	179	9
BUS. LOOP 55 OVER SALT CREEK		CONTRACT NO. 72789		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		