

**PAVING SCHEDULE**

LOCATION	SUBBASE GRANULAR MATERIAL, TYPE A 8 INCH	SUBBASE GRANULAR MATERIAL, TYPE B	SUBBASE GRANULAR MATERIAL, TYPE C	HOT-MIX ASPHALT BASE COURSE 10 3/4 IN	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 3/4 IN	HOT-MIX ASPHALT BINDER COURSE 1L-19, NTO	HOT-MIX ASPHALT SURFACE COURSE, MIX D, NTO	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE A	BITUMINOUS MATERIALS, PRIME COAT	AGGREGATE, PRIME COAT	LEVELING BINDER (MACHINE METHOD), NTO	AGGREGATE SHOULDERS, TYPE B, 4 INCH	HOT-MIX ASPHALT SHOULDERS, 8 INCH	HOT-MIX ASPHALT SHOULDERS, 15 1/2 INCH	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SURFACE REMOVAL, 3 INCH	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	TEMPORARY RAMP	SHOULDER RUMBLE STRIPS, 16 INCH	
	SQ YD	TON	TON	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	FOOT	
Business Loop 55 over Salt Creek																					
73+00.00 TO 91+00.00				2027	1456	1231	1072			4.1	38.5	861	351	2754		1059	621	165	25	3100	
91+00.00 TO 96+20.57	5220		356	2839			236			1.9	15.4	157	242	1042	1041					1042	
102+65.46 TO 106+56.05	3916		267	2130			177			1.3	11.4	118	186	771	800					782	
106+56.05 TO 126+00.00				1348	1142	899	1068			4.2	39.6	937	2399	2930		768	438	160	24	3263	
Broadwell																					
8+81.89 TO 9+71.16				231				22		0.2	0.4								5		
10+29.98 TO 11+37.51				407				36		0.2	0.8								7		
Access Rd																					
50+33.00 TO 53+00.00		212						67		0.0	0.2										
53+00.00 TO 56+67.90		197							113												
1050th Ave																					
69+04.16 TO 69+66.08				240				20		0.2	0.5								7		
Pond Parking Lot		415					134			2.4											
Pond Parking Lot North Field Entrance									37												
Pond Parking Lot South Field Entrance									38												
Shared Use Path									531												
Large Pond Shared Use Path Option									343												
TOTAL	9136	824	623	9222	2598	2130	2687	145	1062	14.5	106.8	2073	3178	7497	1841	1827	1059	325	68	8187	
Small Pond Shared Use Path Option									203		PAY 107										

Note: Small Pond Option shown for informational purposes

**GUARDRAIL SCHEDULE**

LOCATION	SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS	GUARDRAIL MARKERS TYPE A	TRAFFIC BARRIER TERMINAL		TERMINAL MARKER DIRECT APPLIED
					TYPE 1 (SPECIAL) TANGENT	TYPE 6	
		FOOT	FOOT	EACH	EACH	EACH	EACH
Business Loop 55 over Salt Creek							
88+31.12 TO 88+81.12	RT				1		1
88+31.12 TO 96+39.27	RT			9			
88+81.12 TO 95+93.62	LT		712.5				
91+75.00 TO 95+79.34	RT	404					
92+13.91 TO 95+85.89	LT	372					
94+18.62 TO 94+68.62	LT				1		1
94+18.62 TO 96+39.27	LT			4			
94+68.62 TO 95+93.62	RT		125.0				
95+93.62 TO 96+39.27	LT					1	
95+93.62 TO 96+39.27	RT					1	
102+46.77 TO 102+92.42	LT					1	
102+46.77 TO 102+92.42	RT					1	
102+46.77 TO 106+54.92	LT			6			
102+46.77 TO 121+29.92	RT			15			
102+92.42 TO 106+04.92	LT		312.5				
102+92.42 TO 120+79.92	RT		1787.5				
103+00.89 TO 109+99.60	LT	699					
103+06.85 TO 104+34.22	RT	127					
106+04.92 TO 106+54.92	LT				1		1
120+79.92 TO 121+29.92	RT				1		1
TOTAL		1602	2937.5	34	4	4	4

**PATCHING SCHEDULE**

LOCATION	SIDE	PAVEMENT PATCHING TYPE II, 11 INCH	CLASS D PATCHES	
			TYPE III, 11 INCH	TYPE IV, 11 INCH
		SQ YD	SQ YD	SQ YD
Business Loop 55 over Salt Creek		100		
85+12	LT		17	
86+76	LT		17	
88+39	LT		17	
90+69	LT/RT		22	
112+89	RT			33
122+48	LT/RT			172
TOTAL		100	73	205

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**  
PAVING, GUARDRAIL, & PATCHING

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -
1:\06103\cad\1\plans\005.D672789-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 5/23/2013 4:31:36 PM		DATE -	REVISED -

SCALE: NONE SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7706	23(B-1)	LOGAN	179	24
BUS. LOOP 55 OVER SALT CREEK			CONTRACT NO. 72789	
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	

LAST SAVED = 5/23/2013  
PEN TABLE = V8-HA-F-141  
PLOT DRIVER = TR-18pdf-Block-Half.plt