

DRAINAGE SCHEDULE

LOCATION	SIDE	PIPE CULVERTS				PIPE DRAINS	INLETS		PRECAST REINFORCED CONCRETE FLARED END SECTIONS		METAL END SECTIONS		TRANSVERSE DRAINS COMPLETE
		CLASS A		CLASS D		CORRUGATED STEEL OR ALUMINUM ALLOY 12 IN FOOT	TYPE D INLET BOX EACH	TYPE F INLET BOX EACH	12 IN EACH	30 IN EACH	12 IN EACH	24 IN EACH	
		TYPE 1	TYPE 2	TYPE 1	TYPE 2								
		12 IN FOOT	30 IN FOOT	24 IN FOOT	24 IN FOOT								
Business Loop 55 over Salt Creek													
91+50.00	-											1	
96+30.00	RT				10		1			1			
102+56.00	RT				10		1			1			
104+95.00	RT				10			1		1			
115+41.93	LT										1		
122+45.00	LT/RT		130						2				
Access Road													
55+75.00	LT/RT			50							2		
Pond Parking Lot	LT/RT	30							2				
	TOTAL	30	130	50	12	30	2	1	2	2	3	3	1

PIPE UNDERDRAINS SYSTEM SCHEDULE

LOCATION	SIDE	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS
Business Loop 55 over Salt Creek				
80+00.00 TO 84+00.00	LT	400		
84+00.00			13	1
80+00.00 TO 84+00.00	RT	393		
84+00.00			13	1
84+00.00 TO 88+00.00	LT	403		
88+00.00			13	1
84+00.00 TO 88+00.00	RT	397		
88+00.00			45	1
88+00.00 TO 90+31.37	LT	240		
90+31.37			56	1
88+28.00 TO 91+66.00	RT	332		
91+66.00			30	1
94+87.00			13	1
94+96.00 TO 96+20.00	RT	117		
94+96.00			13	1
102+66.00 TO 106+56.00	RT	370		
106+56.00			13	1
	TOTAL	2967	209	9

PAVEMENT MARKING SCHEDULE

LOCATION	MODIFIED URETHANE PAVEMENT MARKING					PREFORMED PLASTIC PAVEMENT MARKING, TYPE B					RAISED REFLECTIVE PAVEMENT MARKER		GROOVING FOR RECESSED PAVEMENT MARKING		
	LINE 5"		LINE 6"	LINE 12"	LETTERS AND SYMBOLS WHITE	INLAID - LINE 5"	INLAID - LINE 6"	INLAID - LINE 12"	INLAID - LINE 24"	INLAID - LETTERS AND SYMBOLS WHITE	MARKER REMOVAL	MARKER	6"	7"	
	WHITE	YELLOW	WHITE			FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	FOOT	FOOT	
	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	FOOT	FOOT	
Business Loop 55 over Salt Creek															
73+14.08 TO 75+14.08			200											200	
73+14.08 TO 78+96.41											46				
73+14.08 TO 79+66.90	1155	2364		587		617	91	196					3519		
73+35.24													15.6		
73+50.00 TO 96+20.57											60				
74+00.00 TO 95+83.00										56					
74+22.38													15.6		
75+09.95													15.6		
76+96.41 TO 78+96.41			200											200	
76+99.82													15.6		
77+87.14													15.6		
78+75.20													15.6		
79+66.90 TO 84+34.54	931	1560				454	47	166					2491		
80+35.01 TO 82+35.01			200											200	
80+35.01 TO 83+95.00											23				
80+56.19													15.6		
81+43.92													15.6		
82+30.38													15.6		
84+20.00 TO 96+20.57	2401	4802				1201		1046			60		7203		
84+34.54 TO 96+20.57	1613	2580											4193		
96+20.57 TO 102+65.46	4080	8128				2032		1709					12208		
102+65.46 TO 126+00.00											196				
103+05.17 TO 124+50.00										56					
122+97.30 TO 126+00.00	606	557				303							1163		
Broadwell															
8+81.69 TO 9+42.19		122												122	
9+41.15														12	
10+55.31 TO 11+37.50		164												164	
10+56.43														21	
1050th Ave															
69+04.16 TO 69+46.65		84												84	
69+46.65														16	
Pond Parking Lot	442			9.2											
	TOTAL	11228	20361	600	587	9.2	4607	138	3117	49	140.4	112	385	31147	600
		31589													

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION	OFFSET	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
		EACH
Business Loop 55 over Salt Creek		
87+00.00	85' RT	1
92+00.00	86.20' LT	1
92+47.68	210' RT	1
95+78.35	150' RT	1
98+00.00	170' RT	1
101+00.00	170' LT	1
101+68.74	266.27' LT	1
103+50.00	150' RT	1
105+00.00	124' RT	1
107+00.00	106' RT	1
109+00.00	100' RT	1
110+15.24	132.19' LT	1
112+00.00	100' RT	1
112+84.29	120' RT	1
114+79.59	97.12' RT	1
115+00.00	95' RT	1
121+50.00	95' RT	1
122+00.00	140' RT	1
122+59.39	81.01' RT	1
	TOTAL	19

LAST SAVED = 5/23/2013
 PEN TABLE = V8-H4-C-141
 PLOT DRIVER = TR-18pdf-Block-Half.plt

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -
I:\06103\cad\l\plans\005.D672789-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 5/23/2013 4:31:38 PM		DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
DRAINAGE, PIPE UNDERDRAINS SYSTEM, PAVEMENT MARKING, & RIGHT-OF-WAY MARKERS			
SCALE: NONE	SHEET NO. 3 OF 5 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7706	23(B-1)	LOGAN	179	26
BUS. LOOP 55 OVER SALT CREEK			CONTRACT NO. 72789	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				