

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		MADISON 80% FED 20% STATE 0005	ST. CLAIR 80% FED 20% STATE 0005	CODE NO	ITEM	UNIT		MADISON 80% FED 20% STATE 0005	ST. CLAIR 80% FED 20% STATE 0005
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	3.2	12.8	67100100	MOBILIZATION	L SUM	1	0.2	0.8
40600300	AGGREGATE (PRIME COAT)	TON	73	15.4	57.6	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.2	0.8
40600990	TEMPORARY RAMP	SQ YD	1328	127.5	1200.5	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.8
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4988	1284	3704	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5
44213100	PAVEMENT FABRIC	SQ YD	239	67	172	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.2	0.8
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	48478	10263.3	38214.7	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5	0.5
44201053	CLASS B PATCHES, TYPE IV, 17 INCH	SQ YD	120		120	* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	2970	1116	1854
44201055	CLASS B PATCHES, TYPE II, 17 INCH	SQ YD	148	40	108	* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	508		508
44201299	DOWEL BARS 1 1/2"	EACH	602	160	442	* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45954	6499	39455
44213200	SAW CUTS	FOOT	1776	468	1308	* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	662		662
44213204	TIE BARS 3/4"	EACH	90	25	65	* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	864	66	798
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1036	234.3	801.7	* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	105	33	72
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	2	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11863	2422.7	9440.3
						+20076600	TRAINEES	HOUR	500	250	250
						+20076604	TRAINEES, TRAINING PROGRAM GRADUATE	HOUR	500	250	250

\*SPECIALTY ITEM <sup>15</sup> + 0042

FILE NAME *	USER NAME * millerra	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 9166	SECTION SIORS-3, 9ORS-1	COUNTY *	TOTAL SHEETS 34	SHEET NO. 3
o:\p\work\p\p\d\millerra\40330606\40330606-ahs-plan.dgn	40330606-ahs-plan.dgn	DRAWN -	REVISED -							
PLOT SCALE * 100.0000 ' / in.		CHECKED -	REVISED -							
PLOT DATE * 5/10/2013		DATE -	REVISED -							
						SCALE: SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 76G36 <small>ILLINOIS FED. AID PROJECT</small>		