

PAVEMENT MARKING SCHEDULE															
LOCATION				THERMOPLASTIC PAVEMENT MARKING - LINE 6"			LETTERS & SYMBOLS (SQ FT.)	TEMPORARY PAVEMENT MARKING - LINE 6"			SHORT TERM PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT.)
STATION	TO	STATION	LANES	WHITE SKIP DASH (FT.)	SOLID YELLOW (FT.)	SOLID WHITE (FT.)		WHITE SKIP DASH (FT.)	SOLID YELLOW (FT.)	SOLID WHITE (FT.)	WHITE SKIP DASHES (FT.)	EDGE LINE (FT.)	REMOVAL (EA.)	PLACED (EA.)	
1350+60.00	TO	1355+60.00	NB	130	500	500	4	130	500	500	144	144	16	16	661
1350+87.00	TO	1355+76.00	SB	130	489	489	4	130	489	489	144	144	16	16	650
SUBTOTAL				260	989	989	8	260	989	989	288	288	32	32	1311
TOTAL				2238			8	2238			576		32	32	1311

PIPE DRAINS SCHEDULE								
LOCATION					SHOULDER REMOVAL AND REPLACEMENT 5"	CONCRETE HEADWALLS FOR PIPE DRAINS	PIPE UNDERDRAINS, 4"	PIPE UNDERDRAINS, 4" (SPECIAL)
STATION	TO	STATION	LANES	LT/RT	FOOT	EACH	FOOT	FOOT
1350+60.00	TO	1355+60.00	NB	LT	500.00		500	
1350+60.00	TO	1355+60.00	NB	RT			500	
1350+87.00	TO	1355+76.00	SB	LT	489.00		489	
1350+87.00	TO	1355+76.00	SB	RT			489	
1351+42.00			NB	RT		2		30
1354+77.00			NB	RT		2		60
1351+73.00			SB	LT		2		36
1355+00.00			SB	LT		2		60
TOTAL					989	8	1978	186

TEMPORARY RAMP SCHEDULE						
STATION	TO	STATION	LENGTH (FT.)	LANE	WIDTH (FT.)	AREA (SQYD.)
1350+60.00	TO	1350+66.67	6.7	NB	42	31.13
1355+53.33	TO	1355+60.00	6.7	NB	42	31.13
1350+89.33	TO	1350+96.00	6.7	NB	42	31.13
1355+24.00	TO	1355+30.67	6.7	NB	42	31.13
1350+87.00	TO	1350+93.67	6.7	SB	40	29.64
1355+69.33	TO	1355+76.00	6.7	SB	40	29.64
1351+16.33	TO	1351+23.00	6.7	SB	40	29.64
1355+40.00	TO	1355+46.67	6.7	SB	40	29.64
SUBTOTAL						243.08
TOTAL						243

NOTE: LEFT/RIGHT (LT/RT) IS DEFINED LOOKING UPSTATION.