

COUNTY:	WILLIAMSON
LOCATION:	URBAN
ROUTE:	F. A. P. 331 (IL 13)
FUNDING:	80% FEDERAL 20% STATE
WORK TYPE:	ROADWAY SAFETY
CONSTRUCTION TYPE CODE	0003 0021

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	2	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	3	3	
54248510	CONCRETE COLLAR	CU YD	4.9	4.9	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1621	1621	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	189	189	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	532	532	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	390	390	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	373	373	
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	790	790	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3019	3019	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1723	1723	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1163	1163	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	444	444	
55100300	STORM SEWER REMOVAL 8"	FOOT	24	24	

FILE NAME : D:\78258-sh1-500-06.dgn
CH2MHILL

USER NAME : mfox	DESIGNED - KN	REVISED -
PLOT SCALE : 2.0000' / 1"	DRAWN - AS	REVISED -
PLOT DATE : 3/11/2013	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 6 OF 16 SHEETS	STA.	TO STA.

F.A.P. RTE. 331	SECTION (I-49-2, N-4, TS-4)	COUNTY WILLIAMSON	TOTAL SHEETS 381	SHEET NO. 11
DRAWING NO. 500-06		CONTRACT NO. 78258		
ILLINOIS FED. AID PROJECT				