

COUNTY:	WILLIAMSON
LOCATION:	URBAN
ROUTE:	F. A. P. 331 (IL 13)
FUNDING:	80% FEDERAL 20% STATE
WORK TYPE:	ROADWAY SAFETY
CONSTRUCTION TYPE CODE:	0003 0021

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	8		8
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	7		7
84200804	REMOVAL OF POLE FOUNDATION	EACH	7		7
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1		1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1		1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4081		4081
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2491		2491
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6780		6780
* 87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	6		6
* 87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	4		4
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18		18
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12		12

*SPECIALTY ITEM

FILE NAME :
D978258-shr-500-13.dgn
CH2MHILL

USER NAME : rfox
DESIGNED - KN
DRAWN - AS
CHECKED -
DATE -
PLOT SCALE : 2.0000 / 1 in.
PLOT DATE : 3/11/2013

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 13 OF 16 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-4)R-2, R-4, TS-4	WILLIAMSON	301	18
DRAWING NO. 300-13			CONTRACT NO. 78258	
ILLINOIS FED. AID PROJECT				