

PAVEMENT AND SHOULDER SCHEDULE

LOCATION			PROCESSING LIME STABILIZED SOIL MIXTURE 12"	LIME	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SUBBASE GRANULAR MATERIAL, TYPE A 12"	AGGREGATE BASE COURSE, TYPE A 8"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	REMARKS
STATION	TO	STATION	SO YD	TON	SO YD	SO YD	SO YD	TON	GAL	TON	TON	TON	
KIRK LANE													
0+20.00	-	7+05.00	2729	67.5			2,585		2,155	15	352		TRAVEL, TURN LANES, AND SHOULDERS
VENABLE DRIVE													
2+50.00	-	3+31.52			287		256		200	1	35		TRAVEL, TURN LANES, AND SHOULDERS
PLAZA DRIVE EAST													
100+25.46	-	100+93.81			416		357		320	2	49		TRAVEL, TURN LANES, AND SHOULDERS
BRENTWOOD DRIVE													
7+80.00	-	9+88.00			705		628		517	4	86		TRAVEL, TURN LANES, AND SHOULDERS
COMMERCE DRIVE													
18+45.00	-	19+93.81			485		437		363	2	59		TRAVEL, TURN LANES, AND SHOULDERS
SHEET TOTALS			2729	67.5		1893		4263		3555	24	582	
SHEET TOTALS FROM PAVMT SCH 1			15605	386.2	33522	3429		24628	634	23536	234	2153	39
PROJECT TOTALS			18,334	453.8	33,522	5,322		28,891	634	27,091	258	2,735	39

NOTES:

1. FOR ADDITIONAL QUANTITY FOR SUBBASE GRANULAR MATERIAL, TYPE A 8" SEE DRAWING NO. SCH-15.
2. FOR ADDITIONAL QUANTITY FOR BITUMINOUS MATERIALS (PRIME COAT) SEE DRAWING NO. SCH-15.
3. FOR ADDITIONAL QUANTITY FOR AGGREGATE (PRIME COAT) SEE DRAWING NO. SCH-15.

FILE NAME =	USER NAME = moesbl	DESIGNED - KN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT AND SHOULDER SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pripdat\holliegl\0333666\097258-shd-SCH-02.dgn		DRAWN - AS	REVISED -			331	11-40R-2, N-4, TS-4	WILLIAMSON	381	44
CH2MHILL	PLOT SCALE = 2.0000' / 1" /	CHECKED -	REVISED -			DRAWING NO. SCH-02		CONTRACT NO. 78258		
	PLOT DATE = 6/26/2013	DATE -	REVISED -		SCALE:	SHEET NO. 2 OF 45 SHEETS		STA.	TO STA.	
ILLINOIS FED. AID PROJECT										