

REMOVAL SCHEDULE

LOCATION			CONCRETE HEADWALL REMOVAL EACH	PIPE CULVERT REMOVAL FOOT	STORM SEWER REMOVAL 8" FOOT	STORM SEWER REMOVAL 12" FOOT	STORM SEWER REMOVAL 15" FOOT	STORM SEWER REMOVAL 18" FOOT	STORM SEWER REMOVAL 24" FOOT	REMOVING INLETS EACH	REMOVAL OF EXISTING STRUCTURES EACH	PIPE UNDERDRAIN REMOVAL (SPECIAL) FOOT	REMARKS
STATION	TO	STATION											
IL 13 WESTBOUND													
444+75.00	LT			14									
448+07.77	LT									1			
451+66.37	LT									1			
457+10.00	RT	457+22.00	RT			13							MEDIAN STORM SEWER
457+22.00	RT									1			MEDIAN INLET
458+58.00	LT			9									
460+51.04	LT			8									
463+43.62	LT			8									
466+72.00	RT									1			MEDIAN INLET
471+26.00	LT			1									
473+60.00	LT	480+37.10	LT									700	
473+60.00	LT			1									PIPE UNDERDRAIN HEADWALL
478+50.00	LT			1									PIPE UNDERDRAIN HEADWALL
IL 13 EASTBOUND													
448+06.04	RT									1			
451+63.96	RT									1			
455+93.00	RT			1									
460+99.45	RT				10								
471+25.81	RT			1									
PLAZA DRIVE WEST													
8+80.37	LT	9+14.63	LT		34								
9+94.15	RT	10+05.54	RT	1	10								
10+11.27	RT	10+41.25	RT			26							
10+10.31	RT									1			
10+42.21	RT									1			
10+25.62	LT				4					1			
10+25.74	LT				4					1			
12+23.88	LT				2								15" CMP
12+33.85	LT				8								42" CPP
COMMERCIAL DRIVE													
1+21.67	RT						13			1			
1+23.33	RT					32							
1+23.33	RT							34					
1+26.64	LT									1			
3+30.63	LT				18								
CITY STREET NORTHWEST													
0+12.18										1			
DIVISION STREET NORTH													
0+50.00	RT									1			
6+47.60	LT			1							1		4' X 4' BOX CULVERT
6+47.60	RT			1									
6+63.27	LT				10					1			
6+64.93	RT				11					1			
15+97.48	LT			1									
16+11.30	LT						11			1			
16+11.42	RT						11			1			
15+94.50	RT								20				
15+98.77	RT	16+22.01	RT			24							
DIVISION STREET SOUTH													
1+37.72	LT									1			
1+37.02	LT	2+27.01	LT				89						
1+76.70	RT						30			1			
1+76.70	RT	2+59.27	RT		84								
1+77.83	RT									1			
1+77.83	RT	2+04.33	RT				33						
SHEET TOTALS			9	234	24	223	35	34	20	21	1	700	

REVISSED SHEET 65-10

FILE NAME - c:\p\work\10\dat\10\ancon\10\0330020.D	USER NAME - brandon.p 78256\shh\SCH-32.dgn	DESIGNED - KN DRAWN - AS	REVISIONS - REVISIONS - REVISIONS - REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	REMOVAL SCHEDULE	SCALE: SHEET NO. 32 OF 45 SHEETS STA. TO STA.	F.A.P. RTE. 331 SECTION 01-4(R)-2, N-4, 1S-4 COUNTY WILLIAMSON TOTAL SHEETS 381 SHEET NO. 74 DRAWING NO. SCH-32 CONTRACT NO. 78256 ILLINOIS FED. AID PROJECT
---	---	-----------------------------	--	---	-------------------------	---	---

