

# STORM SEWER SCHEDULE

LOCATION				STORM SEWERS, CLASS A											PRECAST REINFORCED CONCRETE FLARED END SECTIONS						CONCRETE COLLAR CU YD	POROUS GRANULAR BACKFILL CU YD	TRENCH BACKFILL CU YD	REMARKS
				TYPE 1					TYPE 2															
				12"	15"	18"	24"	36"	12"	18"	24"	36"	42"	12"	18"	24"	36"	42"	12"	15"				
STATION	TO	STATION	OFFSET	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH				
<b>IL13 WESTBOUND</b>																								
443+00	-	444+75	LT							167											1		45	
4+00 PLAZA W	-	444+75	LT	19																			24	
444+75	-	446+30	LT							149														102
446+30	-	448+05	LT						169															108
448+05	-	449+85	LT						174															128
449+85	-	451+67	LT										176											137
451+67	-	454+00	LT										227											197
454+00	-	455+72	LT										168											150
456+65		457+00	LT			33																	17	
457+00		457+77 EX 5X5	LT									76								0.32			72	CONNECT TO EX 5X5 RCB
457+77 EX 5X5		458+57	LT									75								0.44			114	CONNECT TO EX 5X5 RCB
12+72 PLAZA W	-	458+57	LT	7																			5	
458+57	-	460+51	LT									189												245
14+63 PLAZA W	-	460+51	LT	3																			2	
460+51	-	461+97	LT									140												175
461+97	-	463+43	LT									141												134
463+43	-	464+50	LT	104																			103	
17+55 PLAZA W	-	463+43	LT	6																			4	
<b>IL 13 EASTBOUND</b>																								
456+81	-	456+82	RT	9																			14	#35 - #37
456+82	-	457+95	RT				110																146	
457+95	-	459+47	RT									146												125
459+47	-	461+00	RT									147												120
461+00	-	463+50	RT								245													169
<b>IL13 MEDIAN</b>																								
457+10 EX 5X5	-	457+25	MD									13								0.32			14	CONNECT TO EX 5X5 RCB
457+25	-	458+85	MD				157																120	
458+85	-	460+20	MD				132																131	
460+20	-	460+20 North	MD								8												12	#55 - #53
460+20	-	460+20 South	MD								9												14	#55 - #57
460+20	-	461+00	MD								77												82	
461+00	-	461+00	MD								4												8	#59 - #61
461+00	-	462+70	MD								165													187
462+70	-	465+13	MD								237													246
466+72	-	467+09	MD	32																				14
467+09	-	469+25	MD	210																				90
<b>COMMERCIAL DRIVE</b>																								
5X5 HEADWALL	-	1+24.50	RT					26															6	FOR DETAILS, SEE DN. CD-01
1+25	-	456+81.50 IL 13						80															60	#31 - #37
3+30	-	457+95 IL 13	LT	23																			12	
6+30	-	461+00 IL 13	LT	2																				2
<b>CITY ST SOUTHWEST</b>																								
3+50	-	3+50				52																	4	
3+50	-	3+11 CITY ST S	RT									87											75	
<b>CITY STREET SOUTH</b>																								
0+70		1+45	LT	70																				31
1+45	-	1+50	LT	6																				3
1+45	-	2+34	LT	83																				26
4+90 DIVISION S.	-	3+12								242														189
3+12	-	5+50	LT							232												1		334
<b>SHEET TOTALS</b>				<b>574</b>	<b>52</b>	<b>322</b>	<b>216</b>	<b>343</b>	<b>790</b>	<b>745</b>	<b>750</b>	<b>835</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>2</b>	<b>1.08</b>	<b>1496</b>	<b>2500</b>	

FILE NAME = D978258-sh1-SCH-43.dgn  
**CH2MHILL**

USER NAME = mfox	DESIGNED - KN	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN - AS	REVISED -
PLOT DATE = 1/31/2013	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STORM SEWER SCHEDULE**

SCALE: SHEET NO. 43 OF 45 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-4)R-2, N-4, TS-4	WILLIAMSON	381	85
DRAWING NO. SCH-43		CONTRACT NO. 78258		
ILLINOIS FED. AID PROJECT				