

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW PIT SHRINKAGE FACTOR	BORROW EXCAVATION	REMARKS
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
KIRK LN								
7+05 TO 26+75	8002	17.5	6599	7603	-1004	25	1339	
TOTALS	8002						1339	

REMOVAL SCHEDULE

LOCATION STATION TO STATION	PIPE CULVERT REMOVAL	REMARKS
	FOOT	
KIRK LN		
8+07	43	
TOTALS	43	

TREE REMOVAL SCHEDULE

STATION	LT/RT	OFFSET	TREE REMOVAL
KIRK LN		FEET	ACRE
7+05 TO 8+24	LT	0.0 TO 36	0.06
7+05 TO 8+20	RT	0.0 TO 25	0.06
7+70 TO 8+20	RT	25 TO 65	0.04
8+20 TO 9+63	RT	12 TO 37	0.08
12+60 TO 13+18	LT	25 TO 55	0.03
13+43 TO 26+89	CL	0 TO 48	2.98
24+00 TO 26+89	LT	48 TO 88	0.13
26+00 TO 26+89	RT	48 TO 173	0.12
TOTALS			3.5

TEMPORARY DITCH CHECKS SCHEDULE

LOCATION STATION	TEMPORARY DITCH CHECKS	LOCATION STATION	TEMPORARY DITCH CHECKS	LOCATION STATION	TEMPORARY DITCH CHECKS
	FOOT		FOOT		FOOT
KIRK LN LT					
7+50	8	26+00	8	20+10	8
8+50	8			20+70	8
10+00	8	KIRK LN RT		21+30	8
11+50	8			22+50	8
13+50	8	7+50	8	23+25	8
14+80	8	8+30	8	23+50	8
16+00	8	9+60	8	23+75	8
16+75	8	10+90	8	24+00	8
17+75	8	11+20	8	24+25	8
18+50	8	12+50	8	24+50	8
19+50	8	13+80	8	25+70	8
20+50	8	14+50	8	26+00	8
21+50	8	15+30	8	26+30	8
22+50	8	16+10	8		
23+25	8	16+75	8		
23+50	8	17+75	8		
23+75	8	18+30	8		
24+00	8	18+90	8		
24+25	8	19+20	8		
24+50	8	19+50	8		
SUBTOTALS	160		136		104
TOTAL			400		

NOTE: "THE ACTUAL DITCH CHECK LOCATION AND QUANTITY IS TO BE DETERMINED BY THE ENGINEER. THE LOCATIONS PROVIDED IN THE SCHEDULE ARE APPROXIMATE TO ESTABLISH A PLAN QUANTITY"

FILE NAME =	USER NAME = brandonja	DESIGNED -	REVISED -
ci:\pw\work\p\dot\brandonja\0292803\78298-shtb-tyo-sch-ties.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/29/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EARTHWORK, REMOVAL, TEMPORARY DITCH
CHECKS, AND TREE REMOVAL SCHEDULES

SCALE: SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-3)R-4	WILLIAMSON	62	14
CONTRACT NO. 78298			ILLINOIS FED. AID PROJECT	