



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 17, 2019

SUBJECT: Route Kickapoo Trail  
Section 08-F3000-03-BT  
Vermilion County  
Contract No. 91581  
Item 30  
August 2, 2019 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheet 4 of the Plans**
- 2. Added page 76C to the Special Provisions**
- 3. Revised the Index to the Special Provisions**
- 4. Revised the Schedule of Prices**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.  
Bureau Chief  
Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

## INDEX TO SPECIAL PROVISIONS (continued)

<u>ITEM</u>	<u>PAGE</u>
Pedestrian Truss Superstructure	5
Remove Sign (Special)	9
Seeding (Special)	10
Identification and Disposal of Existing Railroad Ties	16
Storm Sewers to be Cleaned, 15"	17
Structural Repair of Concrete	17
Status of utilities to be adjusted	18
SWPPP with attachments	19
General NPDES Permit ILR10	27
Routine On-Site Wetland Determination	45
Bureau of Local Roads and Streets LR 107-4	55
Hot-Mix Asphalt – Required Field Tests	56
Non-Vertical Impact Roller For Hot-Mix Asphalt	57
Pneumatic-Tired Roller For Hot-Mix Asphalt	58
Incidental Take Authorization (ITA)	59
Biological Resources Review	70
Natural Resources Review	74
IDOT TPG	76A
Removal and Disposal of Regulated Substances	76C

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Work Areas.** The excavated soil and groundwater within the work areas listed below shall be managed as non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

### **Site- Trail Alignment - Former CSX Railroad Right-Of-Way**

- All excavation planned on the property formerly known as the abandoned CSX Railroad Right-of-Way. The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(c). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, Indeno(1, 2, 3-cd)pyrene, 1,2 Dibromo-3-Chloropropane, Alpha BHC, Gamma BHC, Dieldren, Dalapon, Arsenic, Lead and Selenium.

### **Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following PESA Sites:

#### **Former Abandoned CSX Railroad Right-of-Way.**

Additional information on the above sites collected during the Phase I Engineering process is available through the Local Participating Agency (LPA).