

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	POPE		60	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
IDNR PROJECT NO.	05-06-008			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
50300255	CONCRETE SUPERSTRUCTURES	CU YD	50
50300265	SEAL COAT CONCRETE	CU YD	0.4
50300300	PROTECTIVE COAT	SQ YD	95
50300510	RUSTICATION FINISH	SQ FT	270
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,550
51201400	FURNISHING STEEL PILES HP10X42	FOOT	50
51202305	DRIVING PILES	FOOT	50
51203400	TEST PILE STEEL HP10X42	EACH	1
51500100	NAME PLATES	EACH	1
542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	132
54213873	STEEL END SECTIONS 18"	EACH	5
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	20
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	90
60255500	MANHOLES TO BE ADJUSTED	EACH	4
60260100	INLETS TO BE ADJUSTED	EACH	1
60600095	CLASS SI CONCRETE (OUTLETS)	CU YD	5
60600605	CONCRETE CURB, TYPE B	FOOT	110
60602800	CONCRETE CUTTER, TYPE B	FOOT	320
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	200
67100100	MOBILIZATION	LSUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	178
72900100	METAL POST, TYPE A	FOOT	45

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
73000100	WOOD SIGN SUPPORT	FOOT	336
* 78001100	PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	35
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,470
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	90
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	160
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	135
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0077740	WOOD GUARD RAIL	FOOT	330
X0325727	WOOD POST SPECIAL	EACH	175
* A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8
* A2007116	TREE, QUERCUS RUBA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	15
* D2001572	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 6' HEIGHT BALLED AND BURLAPPED	EACH	4
XX002173	TREATED TIMBER RAIL	FOOT	82
XX004371	INLETS, TYPE B WITH TYPE 61 GRATE	EACH	1
X0323378	CONCRETE PARKING BLOCKS	EACH	18
X0324740	FURNISHING AND INSTALLING SIGNS	EACH	13
X0974300	SIGN REMOVAL	EACH	1
X0325817	GATE SPECIAL, 10'	EACH	1
X0325818	GATE SPECIAL, 12'	EACH	1
X0325819	GATE SPECIAL, 20'	EACH	1
X0325820	GATE SPECIAL, 25'	EACH	1

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IDOT / IDNR
 DIXON SPRINGS STATE PARK

SCALE: VERT.
 HORIZ.
 DATE: 12/08/06

DRAWN BY: DRR
 CHECKED BY: RGD