

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS NO.
	POPE	ILLINOIS	60
STA.	TO STA.	FED. AID PROJECT	5
		IDNR PROJECT NO. 05-06-008	

TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION	UNIT
PICNIC AREA ROAD - STA 9+87, LT	15
PICNIC AREA ROAD	
STA 82+12, LT	12
STA 85+81, RT	8
STA 85+84, RT	8
STA 85+87, RT	8
SHELTER NO. 2 ROAD - STA 11+17, LT	6
MAIN ROAD NORTH	
STA 31+77, LT	12
STA 41+16, RT	12
IL RTE 146	
STA 102+66, LT	8
STA 102+78, LT	10
STA 102+98, LT	12
STA 103+03, LT	10
STA 103+14, LT	10
STA 103+21, LT	15
STA 103+32, LT	10
STA 103+77, LT	6
STA 103+85, LT	12
<b>TOTAL</b>	<b>174</b>

TREE REMOVAL (OVER 15 UNITS DIAMETER)	
LOCATION	UNIT
PICNIC AREA ROAD	
STA 9+52, LT	24
STA 12+33, RT	26
POOL HOUSE ROAD	
STA 82+91, LT	32
STA 86+43, LT	24
MAIN ROAD NORTH	
STA 30+28, RT	24
STA 30+56, RT	24
STA 37+88, LT	24
STA 41+48, RT	18
STA 43+17, RT	18
STA 43+42, RT	18
IL RTE 146	
STA 103+22, LT	18
<b>TOTAL</b>	<b>250</b>

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
LOCATION		SQ YD
MAIN ENTRANCE ROAD	STA 10+00	251
POOL HOUSE ROAD	STA 80+51 TO STA 81+23.5, LT	100
MAINTENANCE BUILDING ROAD		71
SITE SUPERINTENDANT ENTRANCE ROAD	STA 100+12.40	66
<b>TOTAL</b>		<b>488</b>

PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT		
LOCATION		SQ YD
PICNIC AREA ROAD	STA 11+00, RT	27
SITE SUPERINTENDANT ENTRANCE ROAD	STA 103+76.5, LT	15
GROUP CAMP ROAD	STA 104+42, RT	29
<b>TOTAL</b>		<b>85</b>

PAVEMENT REMOVAL		
LOCATION		SQ YD
SPRING ENTRANCE ROAD - STA 72+00, LT		380
<b>TOTAL</b>		<b>380</b>

PERIMETER EROSION BARRIER	
LOCATION	FOOT
PICNIC AREA ROAD - STA 9+53.50 (CUL-DE-SAC)	120
POOL HOUSE ROAD - STA 85+80 TO STA 88+00, RT	220
SHELTER NO. 1 ROAD - NORTH AND EAST	75
SOUTH	75
SHELTER NO. 2 ROAD - STA 12+50, RT (PARKING LOT SOUTH SIDE)	125
MAIN ROAD NORTH - STA 39+35 TO STA 40+45, RT	100
<b>TOTAL</b>	<b>715</b>

PIPE CULVERTS AND END SECTIONS							
LOCATION	PIPE CULVERTS, CLASS C, TYPE 1 18"	TRENCH BACKFILL	STEEL END SECTIONS 18"	PIPE CULVERT REMOVAL	INLETS, TYPE B W/ TYPE 61 GRATE	CLASS D PATCHES, TYPE II 9 INCH	INLET AND PIPE PROTECTION
	FOOT	CU YD	EACH	FOOT	EACH	SQ YD	EACH
MAIN ROAD NORTH - STA 38+40	46	4	1	23	1	11	1
CEDAR GROVE CAMPGROUND	40	2	2	40		6	1
MAIN ENTRANCE ROAD	46	4	2	25		11	1
<b>TOTAL</b>	<b>132</b>	<b>10</b>	<b>5</b>	<b>88</b>	<b>1</b>	<b>28</b>	<b>3</b>

BASE PREPARATION AND REPAIR			
LOCATION	PREPARATION OF BASE	AGGREGATE BASE REPAIR	
		SQ YD	TON
LODGE AREA	965		44
CEDAR GROVE CAMPGROUND PADS	3,560		154
POOL HOUSE ROAD STA 85+40 TO STA 88+44	340		16
SHELTER NO. STA 10+05 TO STA 13+09	510		23
PICNIC ROAD STA 10+30 TO STA 15+75	610		28
<b>TOTAL</b>	<b>5,985</b>		<b>265</b>

AGGREGATE BASE COURSE, TYPE B	
LOCATION	TONS
PICNIC AREA ROAD: WIDENING AREAS	326
PARKING AREAS	116
POOL HOUSE ROAD: WIDENING AREAS	138
PARKING AREAS	191
SPRING ENTRANCE ROAD: WIDENING AREAS	76
PARKING AREAS	63
SHELTER NO. 1 ROAD: WIDENING AREAS	157
PARKING AREAS	65
SHELTER NO. 2 ROAD: WIDENING AREAS	31
PARKING AREAS	341
MAIN ROAD NORTH: WIDENING AREAS	154
PARKING AREAS	185
GROUP CAMP ROAD	132
CEDAR GROVE CAMPGROUND: ENTRANCE ROAD	46
CAMPER PADS	770
<b>TOTAL</b>	<b>2,534</b>

BITUMINOUS MATERIAL (PRIME COAT)		
LOCATION		GALLONS
PICNIC AREA ROAD - STA 9+53.50 TO STA 15+75		700
POOL HOUSE ROAD - STA 80+40 TO STA 88+43.70		780
SPRING ENTRANCE ROAD - STA 70+40 TO STA 72+40.7		313
SHELTER NO. 1 ROAD - STA 10+08 TO STA 11+15		280
SHELTER NO. 2 ROAD - STA 10+05 TO STA 13+08.62		558
MAIN NORTH ROAD - STA 27+94.50 TO STA 45+05.33		619
GROUP CAMP ROAD - MAIN ROAD NORTH TO DEAD END		164
CEDAR GROVE CAMPGROUND - ROADWAY		232
- PADS		1,344
SITE SUPERINTENDANT ENTRANCE ROAD - STA 100+12.6 TO STA 104+49.5		80
MAINTENANCE BUILDING ROAD		212
MAIN ENTRANCE ROAD - STA 10+00 TO STA 27+94.50		372
LODGE AREA		385
MAIN ROAD SOUTH - MAIN ROAD NORTH TO SHELTER NO. 2 ROAD		205
CHURCH ENTRANCE ROAD		116
<b>TOTAL</b>		<b>6,360</b>

LEVELING BINDER (MACHINE METHOD), N70		
LOCATION		TON
POOL HOUSE ROAD (BRIDGE NO. 1)	STA 80+45 TO STA 85+78	68
BRIDGE NO. 1 TO MAIN ENTRANCE ROAD		23
SPRING ENTRANCE ROAD	STA 70+32 TO STA 72+40.7	52
MAIN ROAD NORTH	STA 27+94.5 TO STA 33+85.46	40
MAIN ROAD NORTH	STA 34+65.47 TO STA 45+05.33	54
GROUP CAMP ROAD - MAIN ROAD NORTH TO DEAD END		20
SITE SUPERINTENDANT ENTRANCE ROAD	STA 100+12.4 TO STA 104+49.5	31
MAIN ENTRANCE ROAD	STA 10+10 TO STA 27+94.5	156
CHURCH ENTRANCE ROAD		49
MAIN ROAD SOUTH - MAIN ROAD NORTH TO SHELTER NO. 2 ROAD		86
CEDAR GROVE CAMPGROUND ROAD		97
MAINTENANCE BUILDING ROAD-MAIN ROAD TO OFFICE		89
<b>TOTAL</b>		<b>765</b>

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	
LOCATION	TON
PICNIC AREA ROAD - STA 10+30 TO STA 15+75 (ROAD)	107
STA 15+57 TO 15+75, LT (ROAD)	3
STA 15+57 TO STA 15+75, LT (ROAD)	3
SPRING ENTRANCE ROAD - STA 72+00, LT (GRASS ISLAND - PARKING)	20
STA 72+00, RT (WIDENING)	2
POOL HOUSE ROAD - STA 82+06 TO STA 85+25, LT (WIDENING)	24
STA 85+40 TO STA 88+43.70 (ROAD)	65
SHELTER NO. 1 ROAD - STA 10+08 TO STA 10+81 (ROAD)	43
SHELTER NO. 2 ROAD - STA 10+05 TO STA 13+08.62 (ROAD)	68
STA 13+08.62, RT	3
STA 13+08.62, LT	4
MAIN ROAD NORTH - STA 27+94.5 TO PT STA 33+50.99 (WIDENING)	12
STA 34+65.47 TO PC STA 35+77.91 (WIDENING)	7
STA 35+55 TO STA 36+69.68, RT (WIDENING)	2
PC STA 36+69.68 TO PC STA 38+99.35, LT (WIDENING)	7
STA 40+00 TO STA 40+75, RT (WIDENING)	1
STA 40+50 TO STA 41+75, LT (WIDENING)	2
STA 41+25 TO PC STA 43+98.75, RT (WIDENING)	5
STA 44+10 TO STA 44+50, RT (WIDENING)	1
LODGE AREA	122
ADDITIONAL BINDER CEDAR GROVE CAMPGROUND ROAD AT MAINTENANCE ROAD	39
<b>TOTAL</b>	<b>540</b>

AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A		
LOCATION		SQ YD
PICNIC AREA ROAD - STA 9+74.72 TO STA 15+75		1,630
POOL HOUSE ROAD - STA 80+40 TO STA 85+78 (BRIDGE NO. 1)		2,215
STA 85+78 (BRIDGE NO.1 TO MAIN ENTRANCE ROAD)		535
STA 85+40 TO STA 88+43.70		510
SPRING ENTRANCE ROAD - STA 70+42 TO STA 72+40.7		1,910
SHELTER NO. 1 ROAD - STA 10+08 TO STA 11+15		485
SHELTER NO. 2 ROAD - STA 10+05 TO STA 13+08.62		1,305
MAIN ROAD NORTH - STA 27+94.5 TO STA 33+85.46		1,035
STA 34+65.47 TO PC STA 45+05.33		1,850
GROUP CAMP ROAD MAIN ROAD - NORTH TO DEAD END		765
SITE SUPERINTENDANT ENTRANCE ROAD - STA 100+12.4 TO STA 104+49.5		3,775
MAIN ENTRANCE ROAD - STA 10+00 TO STA 27+94.5		3,795
MAIN ROAD SOUTH - MAIN ENTRANCE ROAD TO SHELTER NO. 2 ROAD		2,095
CHURCH ENTRANCE ROAD		1,180
MAINTENANCE BUILDING ROAD - MAIN ENTRANCE ROAD TO OFFICE BUILDING		2,160
CEDAR GROVE CAMPGROUND ROAD - PADS		4,085
- ROAD		2,365
LODGE AREA		965
<b>TOTAL</b>		<b>32,660</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 IDOT / IDNR  
 DIXON SPRINGS STATE PARK

SCALE: VERT.  
 HORIZ.  
 DATE: 12/08/06  
 DRAWN BY: DRR  
 CHECKED BY: RGD