

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	111 RS-5 & 116 B-1	McHENRY	98	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED./20% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1		LOCATION 2	LOCATION 3
				INTERSECTION HPP 1000-2A	TRAFFIC SIGNAL HPP Y031-1F	RESURFACING (3 P) F 1000	SN 056-0017 BRIDGE BHF SFTY-2A
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	5	5			
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	2	2			
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	2	2			
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	90	90			
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	240	240			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	111	111			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	410	410			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	430	430			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	5	5			
60107600	PIPE UNDERDRAINS 4"	FOOT	780	780			
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	9	9			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5			
60255500	MANHOLES TO BE ADJUSTED	EACH	1		1		
60260100	INLETS TO BE ADJUSTED	EACH	2		2		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	21		21		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2		2		
60404950	FRAMES AND GRATES, TYPE 24	EACH	6		6		
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2		2		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	3889	3889			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	4	3	3	
67100100	MOBILIZATION	L SUM	1	0.4	0.3	0.3	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.5	0.3	0.2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14980	4050	10930		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	963.6	891	72.6		

SUMMARY OF QUANTITIES			URBAN 80% FED./20% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1		LOCATION 2	LOCATION 3
				INTERSECTION HPP 1000-2A	TRAFFIC SIGNAL HPP Y031-1F	RESURFACING (3 P) F 1000	SN 056-0017 BRIDGE BHF SFTY-2A
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54554	15324		38886	344
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2583	2440		143	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1482	437		1045	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	246	136		110	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	225			225	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	30		30		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	15		15		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	963.6	891		72.6	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	53812	15324		38488	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2583	2440		143	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1482	437		1045	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	246	136		110	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	248			248	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	30			30	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	403	138		265	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	403	138		265	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	990		990		
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	120		120		
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	166		166		
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	66		66		
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	152		152		
* 81400100	HANDHOLE	EACH	7		7		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4		

* SPECIALITY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	

5/14/2007 11:48:58 AM C:\PROJECTS\60A91\118550.dwg