

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	**	MCHENRY	98	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DRIVEWAY PAVEMENT					
LOCATION	OFFSET	DRIVEWAY PAVEMENT REMOVAL (SQ. YD.)	HMA BASE COURSE, 6" (P.E.)(SQ. YD.)	HMA BASE COURSE, 8" (C.E.)(SQ. YD.)	HMA SURFACE COURSE, MIX "C", N50, 2" (TON)
IL 31					
16+29	RT			16	1.8
16+80	LT	55		71	8
17+35	RT			31	3.5
18+08	RT	71		35	4
18+80	RT	72			
US 12 (N)					
20+69	LT	57			
21+00	RT	65		35	4
21+09	LT	57		41	4.6
21+62	LT	60		41	4.6
22+00	RT	63		68	7.62
22+18	LT	60		41	4.6
22+65	RT	62		76	8.5
22+71	LT	58		41	4.6
23+32	RT	117		131	14.7
23+52	LT	76		77	8.6
24+43	LT	65		94	10.5
25+20	LT	77		107	12
25+44	RT	161		73	8.2
26+60	RT	124		68	7.62
28+20	RT	57	72		8.1
28+81	RT	80	81		9.1
TRYON GROVE RD.					
6+69	RT	24		18	2
8+41	LT			36	4
US 12 (E)					
11+10	LT	65		57	6.4
11+10	RT	69			
11+80	RT	70		81	9.1
11+92	LT	65		118	13.2
12+48	RT	70		92	10.3
13+15	RT	67			
13+19	LT	92		118	13.2
14+40	RT	35		41	4.6
15+22	RT			37	4.1
16+24	LT	57	80		9
TOTAL =		2051	233	1644	210.5

HOT-MIX ASPHALT SHOULDERS, 8"			
STATION - STATION	OFFSET	WIDTH (FT)	AREA (SQ. YD.)
IL 31			
10+00 - 15+26	LT	5	287
10+00 - 13+50	RT	5	196
15+26 - 19+44	LT	6	283
13+50 - 19+44	RT	4	273
US 12 (N)			
20+33 - 25+85	LT	4	287
20+33 - 27+15	RT	10 - 4	558
25+85 - 29+64	LT	5	210
27+15 - 29+64	RT	5	158
TRYON GROVE RD.			
4+92 - 9+64	LT	6 - 11	473
4+92 - 9+64	RT	6	320
US 12 (E)			
10+45 - 14+60	LT	4	193
10+45 - 15+74	RT	6	332
14+60 - 19+40	LT	5	275
15+74 - 19+40	RT	5	205
TOTAL =			4050

AGGREGATE SHOULDERS, TYPE B, 6"			
STATION - STATION	OFFSET	WIDTH (FT)	AREA (SQ. YD.)
IL 31			
10+00 - 15+26	LT	3	175
10+00 - 13+50	RT	3	117
US 12 (N)			
25+85 - 29+64	LT	3	126
27+15 - 29+64	RT	3	83
US 12 (E)			
14+60 - 19+40	LT	3	160
15+74 - 19+40	RT	3	122
TOTAL =			783

PIPE CULVERT REMOVAL		
STATION	OFFSET	LENGTH (FT)
IL 31		
16+36	28' RT	30
16+80	25.5' LT	30
US 12 (N)		
25+50	27' RT	80
26+57	29' RT	56
27+65	-	57
28+22	32' RT	14
US 12 (E)		
13+17	40' LT	62
16+25	42' LT	40
TOTAL =		369

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US 12 (AT ILL 31 & TRYON GROVE)
LOCATION 1
SCHEDULE OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____