

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2006-043 RS	COOK	135	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN  
90% FED./10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X231-2A	BRIDGES X031-2A	BRIDGES X131-2A
<del>55021600</del>	<del>RECP CL III, TYP 2, REIN. CONC. CULVERT, ST. DRAIN, AND SEWER PIPE, CLASS III 12"</del>	<del>FOOT</del>	<del>80</del>			<del>80</del>			
59000200	EPOXY CRACK INJECTION	FOOT	500				300	100	100
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	8			8			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	757			757			
63500105	DELINEATORS	EACH	2385	1193	1202				
64200105	SHOULDER RUMBLE STRIP	FOOT	135,522	67,872	67,650				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	10	10				
67100100	MOBILIZATION	L SUM	1	0.4	0.4		0.2		
<del>70300240</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 6"</del>	<del>FOOT</del>	<del>16,000</del>	<del>8,000</del>	<del>8,000</del>				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,700	850	850				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,600	2,300	2,300				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	174,596	86,159	88,437				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	27,060	13,732	13,328				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6,112	3,132	2,980				
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	37,108	18,554	18,554				
* 78008210	POLYUREA PAVEMENT MARKING, TYPE I, 4"	FOOT	5002	2501	2501				
* 78008220	POLYUREA PAVEMENT MARKING, TYPE I, 5"	FOOT	1,252	626	626				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,710	1,855	1,855				
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	978	489	489				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	99,220	49,610	49,610				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,710	1,855	1,855				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,000	1000					
X0321743	SILICONE JOINT SEALER, 1"	FOOT	107				107		
X0321744	SILICONE JOINT SEALER, 2"	FOOT	1,343				613	260	470
* X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1	0.5	0.5				
* X0322300	ELECTRIC CABLE IN CONDUIT NO.18 4/C, TWISTED, SHIELDED	FOOT	10,133	10,133					
X0322729	MATERIAL TRANSFER DEVICE	TON	37,284	18,672	18,612				
X0322905	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIRS	L SUM	1				1		
X0325114	ADJUSTING DRAINAGE SCUPPERS, TYPE A	EACH	14				6	7	1
<del>X0325303</del>	<del>STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)</del>	<del>SO FT</del>	<del>699</del>	<del>456</del>	<del>243</del>				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	1300				1100	100	100
X0325428	CLASS A PATCHES, TYPE II, 10 INCH (SPECIAL)	SO YD	310						

\* - SPECIALTY ITEMS

PLOT DATE = 5/23/2007  
FILE NAME = #FILEL4  
USER NAME = gdfout

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.I. 94 (I-94)

SCALE: \_\_\_\_\_  
DATE MAY 2007

DRAWN BY DCS  
CHECKED BY \_\_\_\_\_

REV.