

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2HB)M	WINNEBAGO	13	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

Paycode	Description	Unit	Quantity
			90% FED 20% STATE
			SFTY-2A
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	652
20700220	POROUS GRANULAR EMBANKMENT	CU YD	25
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	94
50102400	CONCRETE REMOVAL	CU YD	13
50300100	FLOOR DRAINS	EACH	12
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.6
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4800
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1
50501110	STRUCTURAL STEEL REMOVAL	POUND	4,430
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1610
50800515	BAR SPLICERS	EACH	26
51100100	SLOPE WALL 4 INCH	SQ YD	440
52000110	PREFORMED JOINT STRIP SEAL	FOOT	72
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	50
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	7000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2350
70400100	TEMPORARY CONCRETE BARRIER	FOOT	700
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1400
78300100	PAVEMENT MARKING REMOVAL	SQ FT	270
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	655
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY #1	L SUM	1
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	77
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	20
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	112
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1

Summary of Quantities
 Montague Road over US 20
 FAP 301 (US 20)
 Section (2HB)M
 Winnebago County
 Structure Number 101-0094