

# SUMMARY OF QUANTITIES

F. A. P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	121BR	VERMILION	19	4
STA.		TO STA.		
FED. ROAD DIST. NO.	LENGHT	FED. AID PROJECT		

SUMMARY OF QUANTITIES				S.N. 092-8043 FAP 840 (IL 49) VERMILION COUNTY STA. 796+57.5		S.N. 092-8072 FAP 840 (IL 49) VERMILION COUNTY STA. 806+80.46	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL		RURAL	
				100% STATE	100% STATE	100% STATE	100% STATE
				Y007	Y007		
20200100	EARTH EXCAVATION	CU YD	325.0	3.0	322.0		
20900110	POROUS GRANULAR BACKFILL	CU YD	43.0	0.0	43.0		
21400100	GRADING AND SHAPING DITCHES	FOOT	106.0	65.0	41.0		
28000300	TEMPORARY DITCH CHECKS	EACH	5.0	1.0	4.0		
28000400	PERIMETER EROSION BARRIER	FOOT	260.0	100.0	160.0		
28000500	INLET & PIPE PROTECTION	EACH	1.0	0.0	1.0		
28100105	STONE RIPRAP, CLASS A3	SQ YD	8.0	0.0	8.0		
28101500	RIPRAP, SPECIAL	SQ YD	77.0	0.0	77.0		
44000100	PAVEMENT REMOVAL	SQ YD	80.0	0.0	80.0		
44201383	CLASS C, PATCHES TYPE IV, 12"	SQ YD	80.0	0.0	80.0		
50104300	CONCRETE HEADWALL REMOVAL	CU YD	2.0	2.0	0.0		
51205200	TEMPORARY SHEET PILING	SQ FT	132.0	0.0	132.0		
51500100	NAME PLATES	EACH	1.0	0.0	1.0		
54020803	PRECAST CONCRETE BOX CULVERT 8' X 3' (M273)	FOOT	42.0	0.0	42.0		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	46.0	46.0	0.0		
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5		
X0336900	PRECAST CONCRETE BOX CULVERT END SECTIONS 8' X 3'	EACH	2.0	0.0	2.0		

\* No Specialty Items