

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	92-9 I	VERMILION	8	6

### SCHEDULE OF QUANTITIES

CONTRACT NO. 70657

	DEPTH	STATION	DIRECTION	LANE	LENGTH FT	WIDTH FT	PATCH	PATCH	SAW CUTS FT	PVMT FAB SQYD	TIE BARS EACH	DOWEL BARS EACH
							AREA TYP IV VAR SQYD	AREA TYP IV 10" SQYD				
<b>092-0152</b>	VAR	1238+62.00	EB	PL	150	12	200.0		324.0	200.0	75	10
	10"	1240+12.00	EB	PL	196	12		261.3	392.0	261.3	98	
	VAR	1242+08.00	EB	PL	150	12	200.0		312.0	200.0	75	10
	VAR	1237+97.00	EB	DL	150	12	200.0		239.0	200.0	33	10
	10"	1239+47.00	EB	DL	196	12		261.3	196.0	261.3	0	
	VAR	1241+43.00	EB	DL	150	12	200.0		162.0	200.0	0	10
<b>092-0115</b>	VAR	1318+19.00	EB	PL	150	12	200.0		324.0	200.0	75	10
	10"	1319+69.00	EB	PL	196	12		261.3	392.0	261.3	98	
	VAR	1321+65.00	EB	PL	150	12	200.0		312.0	200.0	75	10
	VAR	1318+01.00	EB	DL	150	12	200.0		192.0	200.0	9	10
	10"	1319+51.00	EB	DL	196	12		261.3	196.0	261.3	0	
	VAR	1321+47.00	EB	DL	150	12	200.0		162.0	200.0	0	10
<b>TOTAL</b>							<b>1600.0</b>	<b>1045.3</b>	<b>3203.0</b>	<b>2645.3</b>	<b>538.0</b>	<b>80.0</b>
<b>USE</b>							<b>1600.0</b>	<b>1046.0</b>	<b>3203.0</b>	<b>2646.0</b>	<b>538.0</b>	<b>80.0</b>