

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	**	13	6

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* - D-6 MEDIAN PROTECTION 2007
 ** - MACOUPIN, MONTGOMERY, SANGAMON, AND LOGAN COUNTIES

SCHEDULE FOR PROPOSED SAFETY IMPROVEMENTS

GENERAL LOCATION	DESCRIPTION OF HAZARD	I-55 STA OF HAZARD	EXISTING MEDIAN WIDTH	EXISTING SHOULDER WIDTH	HAZARD OFFSET FROM EDGE OF PAVEMENT	WIDTH OF HAZARD	LENGTH OF HAZARD	PROPOSED IMPROVEMENT SEE DETAIL	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
		(MILE STA)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(A, B, OR C)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-55 SANGAMON COUNTY																
(6S0841055R079.8)	SIMPLE SPAN SIGN TRUSS (NB MED.)	79.8	86.5	6.0	29.5	3.0	11.0	A	--	--	87.5	4	1	1	1	--
(6S0841055R079.8)	SIMPLE SPAN SIGN TRUSS (NB OUT.)	79.8	--	--	31.3	3.0	11.0	A	--	--	62.5	4	1	1	1	--
(6S0841055L082.1)	SIMPLE SPAN SIGN TRUSS (SB OUT.)	82.1	--	--	30.6	2.3	10.9	A	--	--	75.0	4	1	1	1	--
(6C0841055R083.2)	CANTILEVER SIGN STRUCTURE (NB OUT.)	83.2	--	--	18.5	3.8	4.1	A	--	--	162.5	4	1	1	1	--
(6S0841055L083.7)	SIMPLE SPAN SIGN TRUSS (SB OUT.)	83.7	--	--	30.8	3.0	13.0	A	--	--	87.5	4	1	1	1	--
SN 084-0115	OUTSIDE SHOULDER (SB)	85.6	--	--	20.8	2.5	14.3	A	--	--	75.0	4	1	1	1	--
SN 084-0115	MEDIAN BRIDGE PIER (NB)	85.7	61.8	10.0	30.5	2.5	14.3	A	--	--	87.5	4	1	1	1	--
SN 084-0115	MEDIAN BRIDGE PIER (SB)	85.7	61.8	10.0	28.8	2.5	14.3	A	--	--	87.5	4	1	1	1	--
SN 084-0081	OUTSIDE SHOULDER (SB)	87.1	--	10.0	32.2	2.5	19.4	B	--	--	125.0	4	1	1	1	--
SN 084-0081	MEDIAN PIER (SB)	87.4	63.4	10.0	29.1	2.5	19.4	A	--	--	87.5	4	1	1	1	--
SN 084-0018	MEDIAN SHOULDER (NB)	102.4	--	--	--	--	--	C	--	1	312.5	5	1	1	--	1
SN 084-0017	MEDIAN SHOULDER (SB)	102.5	--	--	--	--	--	C	--	1	312.5	5	1	1	--	1
SN 084-0020	MEDIAN SHOULDER (NB)	104.3	--	--	--	--	--	C	--	1	325.0	5	1	1	--	1
(6C0841055L107.2)	CANTILEVER SIGN STR (SB OUT.)	107.2	--	--	17.5	4.5	4.5	A	--	--	175.0	4	1	1	1	--
I-55 SANGAMON COUNTY SUB-TOTAL:									0.0	3.0	2062.5	59.0	14.0	14.0	11.0	3.0

PLOT DATE = 5/10/2007
 FILE NAME = c:\p\projects\4652406\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAI 55
 SECTION D-6 MEDIAN PROTECTION 2007
 MACOUPIN, MONTGOMERY,
 SANGAMON, LOGAN COUNTIES