

PAVEMENT MARKING SCHEDULE			
STATION	TYPE	PAINT PVT MK LINE 5"	
		WHITE	YELLOW
LT & RT STA. 302+08 TO 490+08	EDGE LINE	37,600 FT	
LT STA. 302+08 TO 309+28	NO PASS		720 FT
RT STA. 302+08 TO 309+28	SKIP DASH		180 FT
STA. 309+28 TO 452+00	SKIP DASH		3,570 FT
RT STA. 452+00 TO 464+14	NO PASS		1,214 FT
LT STA. 452+00 TO 462+15	SKIP DASH		250 FT
LT STA. 462+15 TO 473+43	NO PASS		1,128 FT
RT STA. 464+14 TO 473+43	SKIP DASH		230 FT
STA. 473+43 TO 490+08	SKIP DASH		420 FT
DEDUCT FOR SIDEROAD		(561 FT)	
TOTALS		37,039 FT	7,712 FT

NOTES:

STATIONS ARE APPROXIMATE.

MIXTURE REQUIREMENTS	
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT	
MIXTURE USE(S):	POLY H.M.A S.C., MIX D, N70
AC/PG:	SBS PG 70-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 70
MIXTURE COMP:	IL 9.5 OR 12.5
FRICTION AGG:	MIX "D"

SCHEDULES
FAP 72 (IL 29)
SECTION 5RS-7, 6RS-7
SANGAMON/CHRISTIAN COUNTY