

PAVEMENT MARKING SCHEDULE				
STATION	TYPE	THERMOPLASTIC PAV'T MKG		
		LINE 5"		LINE 6"
		WHITE	YELLOW	WHITE
LOCATION #1				
LT & RT 15+70 TO 0+61	EDGE LINE	3,018 FT		
LT & RT 15+70 TO 15+27	NO PASS		90 FT	
LT 15+27 TO 6+37	SKIP DASH		220 FT	
RT STA. 15+27 TO 6+37	NO PASS		890 FT	
STA. 6+37 TO 0+60	SKIP DASH		140 FT	
STA. 0+00 TO 40+40	SKIP DASH		1,010 FT	
DEDUCT FOR SIDEROAD		(79 FT)		
LOCATION #2				
STA. 1+27 TO 8+35	SKIP DASH		180 FT	
LOCATION #3				
STA. 30+20 TO 31+17	TURN LANE		194 FT	
STA. 320+30+25	TURN LANE			5 FT
STA. 31+17 TO 63+62 *	SKIP DASH		780 FT	
* STA. EQ. - 55+53.41bk=57+00.00ah				
TOTALS		2,939 FT	3,504 FT	5 FT

NOTES:

STATIONS ARE APPROXIMATE.

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
MIXTURE USE(S):	POLY H.M.A S.C., MIX D, N70	H.M.A S.C., MIX C, N50
AC/PG	SBS PG 70-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 70	4.0% @ N DESIGN = 50
MIXTURE COMP:	IL 9.5 OR 12.5	IL 9.5 OR 12.5
FRICTION AGG:	MIX "D"	MIX "C"

SCHEDULES  
 FAP 325(IL 16), FAU 7935(IL 29), FAP 322(US 51)  
 SECTION D-6 PANA CNTR MAINT RES 2008  
 CHRISTIAN COUNTY