CONTRACT NO. 74003

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	101B-1	WABASH	34	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING

LOCATION	SIDE	WIDTH	BASE COURSE WIDENING 10"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE IL-19, N70	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N70	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SHOULDERS 6"	PORTLAND CEMENT CONC PAVEMENT 10"
STATION TO STATION		FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
SN 093-0005 (IL 1) BONPAS CREEK											
STA 146+22.46 (BK) TO STA 148+46.92 (AH)	LT/RT		75							119	24
STA 147+83.00 (AH) TO STA 148+46.92 (AH)	LT/RT			92	0.4		16				
STA 147+83.00 TO STA 148+13.00	LT/RT							87			
STA 148+13.00 TO STA 148+46.92	LT/RT	26				5					
STA 148+46.92 TO STA 148+66.84	LT/RT	10							44.5		
STA 149+93.16 TO STA 150+13.08	LT/RT	10							44.5		
STA 150+13.08 TO STA 150+63.08	LT/RT						12				
STA 150+13.08 TO STA 152+06.75	LT/RT		75							138	
STA 150+13.08 TO STA 150+31.08	LT/RT	26				3					
STA 150+31.08 TO STA 150+63.08	LT/RT	26		73	0.3			92			
TOTAL			150	165	1	8	28	179	89	257	24

PAVEMENT MARKING

LOCATION	SIDE	PAINT PAVEMENT MARKING LINE 4" SOLID WHITE	PAINT PAVEMENT MARKING LINE 6" SKIP DASH YELLOW	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL
STATION TO STATION		FOOT	FOOT	EACH	SQ FT	SQ FT
SN 093-0005 (IL 1) BONPAS CREEK						
STA 144+19.71 TO STA 154+17.53	LT/RT			12		52
STA 144+32.21 TO STA 154+93.00	LT/RT					52
STA 144+19.71 TO STA 147+24.38 (BK)	LT/RT	609			203	111
STA 144+19.71 TO STA 147+24.38 (BK)	CL		76		16	10
STA 144+32.21 TO STA 147+24.38 (BK)	LT/RT					97
STA 147+55.17 (AH) TO STA 154+17.53	CL		166		33	
STA 147+55.17 (AH) TO STA 147+83.00	CL					1
STA 147+55.17 (AH) TO STA 147+83.00	LT/RT					1
STA 147+55.17 (AH) TO STA 154+17.53	LT/RT	1325			442	
STA 147+24.38 (BK) TO STA 144+14.71	CL					
STA 147+55.17 (AH) TO STA 154+17.53	LT/RT					221
STA 147+55.71 (AH) TO STA 153+93.00	LT/RT					213
STA 150+63.08 TO STA 154+17.53	CL					12
STA 150+63.08 TO STA 154+17.53	LT/RT					8
TOTAL		1934	242	12	694	778

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET 1 OF 2

SCALE: VERT. NONE HORIZ. NONE

DATE 06/20/07

DRAWN BY KMO

CHECKED BY SSM

Plot Date: 6/21/2007
Plot Time: 9:21:05 AM
Plotted By: swissendorph
Pen Table: Pen50.tbl
Filename: I:\06059\Cad\Downscope\Bonpas-Construction Plan\04_Schedules.dgn