

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
32B	(8BR-1)B-1	WAYNE	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 096-0020 (US 45)	
				WAYNE COUNTY 100% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A
20200100	EARTH EXCAVATION	CU YD	134	134	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.25	0.25	
28000300	TEMPORARY DITCH CHECKS	EACH	3	3	
28000400	PERIMETER EROSION BARRIER	FOOT	746	746	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
35650500	BASE COURSE WIDENING 10"	SQ YD	354	354	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	31	31	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	58	58	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600990	TEMPORARY RAMP	SQ YD	28	28	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	5	5	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	19	10	9
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	116	116	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	146		146
44000700	APPROACH SLAB REMOVAL	SQ YD	1016	1016	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	297	297	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	60	60	
50300260	BRIDGE DECK GROOVING	SQ YD	144		144
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.6		1.6
50300300	PROTECTIVE COAT	SQ YD	154		154
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1383		1383
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	3250		3250
50800515	BAR SPLICERS	EACH	42		42
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	82		82
50901050	STEEL RAILING, TYPE SM	FOOT	126		126
51500100	NAME PLATES	EACH	1		1
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	70	70	
54213450	END SECTIONS 15"	EACH	4	4	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SUMMARY OF QUANTITIES</b></p> <p align="center">SHEET 1 OF 2</p> <p>SCALE: VERT. N/A HORIZ. N/A DATE 06/20/07</p> <p align="right">DRAWN BY KMO CHECKED BY SSM</p>

Plot Date: 6/20/07  
 Plot Time: 8:45:40 AM  
 Plotted By: korenderzh  
 Pen Table: Idet.tbl  
 Filename: I:\06055\06055\Downscope\Encalloy-Construction Plans\03\_Summary.dgn