

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	08R-11B-1	WAYNE	39	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODED PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 096-0020 (US 45)	
				WAYNE COUNTY 100% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500	500	
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	404	404	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1591	1591	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350	350	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	450	450	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2895	2895	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10	
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1206	1206	
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	281	281	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	252		252
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNIT	SQ FT	299		299
X5030305	CONCRETE WEARING SURFACE	SQ YD	154		154
X0013790	CONSTRUCTION LAYOUT	L SUM	1		
X0325826	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH) SPECIAL	SQ FT	252		252

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 2 OF 2

SCALE: VERT. N/A
DATE 06/20/07

DRAWN BY KMO
CHECKED BY SSM