

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	(8BR-1)B-1	WAYNE	39	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING											
LOCATION	SIDE	WIDTH	BASE COURSE WIDENING 10"	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	HOT-MIX ASPHALT BINDER COURSE IL-19, N70	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N70	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SHOULDERS 6"
STATION TO STATION		FEET	SQ YD	TON	GALLON	TON	SQ YD	TON	TON	SQ YD	SQ YD
SN 096-0020 (US 45) ENDSLEY CREEK											
STA 717+19.95 TO STA 719+21.59	LT		75								
STA 717+29.89 TO STA 719+21.59	LT										66
STA 716+99.69	LT			23							
STA 717+37.25	RT			8							
STA 717+44.42 TO STA 719+21.59	RT		75								62
STA 719+01.59 TO STA 719+21.59	LT/RT	26			29	0.2	14	2.5	5	58	
STA 720+04.59 TO STA 720+24.59	LT/RT	26			29	0.2	14	2.5	5	58	
STA 720+04.59 TO STA 723+08.63	LT		119								103
STA 720+04.59 TO STA 722+06.52	RT		85								66
TOTAL			354	31	58	1	28	5	10	116	297

PAVEMENT MARKING						
LOCATION	SIDE	PAINT PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL
		LINE 4" SOLID WHITE FOOT	LINE 4" SOLID YELLOW FOOT			
STATION TO STATION				EACH	SQ FT	SQ FT
SN 096-0020 (US 45) ENDSLEY CREEK						
STA 716+01.34 TO STA 717+88.09	RT					187
STA 716+01.34 TO STA 718+88.09	LT					230
STA 716+01.34 TO STA 723+24.84	LT/RT	1448		10	482	71
STA 716+01.34 TO STA 723+24.84	CL		1447		724	24
STA 717+19.95 TO STA 722+01.10	LT/RT					321
STA 717+24.53 TO STA 722+06.52	LT/RT					321
STA 720+38.09 TO STA 723+74.84	LT					250
STA 721+38.09 TO STA 723+24.84	RT					187
TOTAL		1448	1447	10	1206	1591

EARTHWORK					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION TO STATION	CU YD	CU YD		CU YD	CU YD
SN 096-0020 (US 45) ENDSLEY CREEK					
STA 716+69.16 TO STA 723+08.63	134	103	25	64	39
TOTAL	134	103		64	39

Plot Date: 6/21/2007  
 Plot Time: 10:16 AM  
 Plot File: S:\Projects\800101\800101.dwg  
 Plot Table: 1001.tbl  
 File Name: I:\06055\Code\Downscope\Endsley-Construction\Figures\Schedule.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
SHEET 1 OF 2

SCALE: VERT. NONE  
HORIZ. NONE  
DATE 06/20/07

DRAWN BY KMO  
CHECKED BY SSM