

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-15,61	WASHINGTON	11	9
STA.		TO STA.		
CONTRACT NO.: 76A38				

PARTIAL DEPTH PATCHING SCHEDULE

STATION	LT/RT	PL/DL	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	PARTIAL DEPTH REMOVAL, 3 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
EAST BOUND							
2935+25							
2948+26	RT	DL	60	12	80.0	80.0	15.7
2969+21	RT	DL	50	12	66.7	66.7	13.1
3019+89	RT	DL	100	12	133.3	133.3	26.1
3091+20	RT	DL	60	12	80.0	80.0	15.7
3170+95	RT	CL	150	2	33.3	33.3	6.5
3285+05	RT	CL	30	2	6.7	6.7	1.3
3407+05	RT	DL	40	2	8.9	8.9	1.7
3538+24	RT	CL	500	2	111.1	111.1	21.8
3669+43	RT	DL	500	2	111.1	111.1	21.8
3809+93	RT	DL	200	2	44.4	44.4	8.7
3955+33	RT	DL	60	2	13.3	13.3	2.6
4105+27	RT	DL	50	12	66.7	66.7	13.1
4257+27	RT	CL	80	2	17.8	17.8	3.5
5781+27	RT	DL	300	2	66.7	66.7	13.1
5936+07	RT	CL	50	2	11.1	11.1	2.2
6093+87	RT	DL	50	2	11.1	11.1	2.2
6254+77	RT	CL	40	2	8.9	8.9	1.7
6417+37	RT	DL	40	2	8.9	8.9	1.7
6579+97	RT	CL	40	2	8.9	8.9	1.7
6743+67	RT	CL	40	2	8.9	8.9	1.7
6908+93	RT	CL	40	2	8.9	8.9	1.7
7074+19	RT	DL	200	2	44.4	44.4	8.7
7242+49	RT	CL	75	2	16.7	16.7	3.3
7410+79	RT	DL	200	2	44.4	44.4	8.7
7580+29	RT	CL	40	2	8.9	8.9	1.7
7750+89	RT	DL	100	2	22.2	22.2	4.4
7924+59	RT	CL	40	2	8.9	8.9	1.7
8098+29	RT	DL	100	2	22.2	22.2	4.4
8273+38	RT	CL	40	2	8.9	8.9	1.7
8449+88	RT	CL	40	2	8.9	8.9	1.7
8657+46	RT	DL	800	2	177.8	177.8	34.8
8876+11	RT	DL	60	2	13.3	13.3	2.6
9097+81	RT	DL	250	12	333.3	333.3	65.3
9334+85	RT	PL	250	12	333.3	333.3	65.3
9575+86	RT	DL	200	12	266.7	266.7	52.3
9809+46	RT	DL	150	12	200.0	200.0	39.2
10055+06	RT	DL	200	12	266.7	266.7	52.3
10307+71	RT	DL	100	12	133.3	133.3	26.1
10565+21	RT	DL	150	12	200.0	200.0	39.2
10834+91	RT	DL	100	12	133.3	133.3	26.1
11106+92	RT	DL	300	12	400.0	400.0	78.4
11391+77	RT	DL	100	12	133.3	133.3	26.1
14616+77	RT	DL	5500	4	2444.4	2444.4	479.1
14940+47	RT	DL	800	12	1066.7	1066.7	209.1
15290+14	RT	DL	30	12	40.0	40.0	7.8
15639+83	RT	CL	30	12	40.0	40.0	7.8
16005+28	RT	CL	100	2	22.2	22.2	4.4
16370+73	RT	DL	100	2	22.2	22.2	4.4
16737+40	RT	DL	80	12	106.7	106.7	20.9
17131+40	RT	DL	100	6	66.7	66.7	13.1
17528+54	RT	DL	100	6	66.7	66.7	13.1
17937+29	RT	DL	40	12	53.3	53.3	10.5
18352+29	RT	DL	60	6	40.0	40.0	7.8
18772+73	RT	DL	300	12	400.0	400.0	78.4
19194+59	RT	DL	150	6	100.0	100.0	19.6
TOTALS					8152.2	8152.2	1597.8

PARTIAL DEPTH PATCHING SCHEDULE

STATION	LT/RT	PL/DL	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	PARTIAL DEPTH REMOVAL, 3 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
WEST BOUND							
3355+52		DL	21	12	28.0	28.0	5.5
3354+45		PL	100	12	133.3	133.3	26.1
3353+98		DL	200	2	44.4	44.4	8.7
3553+40		CL	23944	2	5320.9	5320.9	1042.9
3349+98		DL	1256	2	279.1	279.1	54.7
3324+48		DL	150	2	33.3	33.3	6.5
3318+12		DL	1000	2	222.2	222.2	43.6
3299+52		DL	500	2	111.1	111.1	21.8
3284+96		DL	60	24	160.0	160.0	31.4
3284+96		CL	60	24	160.0	160.0	31.4
3282+32		DL	6	12	8.0	8.0	1.6
3266+26		DL	10	12	13.3	13.3	2.6
3260+52		CL	2280	2	506.7	506.7	99.3
3248+22		DL	3641	2	809.1	809.1	158.6
3243+51		CL	6	30	20.0	20.0	3.9
3220+55		DL	60	12	80.0	80.0	15.7
3196+48		CL	150	12	200.0	200.0	39.2
3191+29		CL	150	12	200.0	200.0	39.2
3048+02		DL	150	12	200.0	200.0	39.2
2996+22		CL	100	12	133.3	133.3	26.1
TOTALS					8662.9	8662.9	1697.9

PAVEMENT MARKING SCHEDULE

	PAINT				RPM REMOVAL (EACH)	REMOVAL WORKZONES PAVEMENT MARKING	
	4" SOLID YELLOW (FEET)	4" SKIP DASH WHITE (FEET)	4" SOLID WHITE (FEET)	SHORT TERM PAVEMENT MARKING (FEET)		REMOVAL WORKZONES PAVEMENT MARKING (SOFT)	
WB Partial Depth	220	6749	7114	344	968	323	
EB Partial Depth	250	1114	11780	70	593	198	
FULL DEPTH RAMPS	733		513		50	17	
WB FULL DEPTH	18	206	1663	25	88	29	
EB FULL DEPTH		599	2731	43	169	56	
						0	
15% ANTICIPATED FAILURE	183	1300	3570	72	280	93	
SUBTOTAL:	1404	9968	27371	554	2148	716	
TOTAL:		38743					

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAI ROUTE 64
SECTION 95-(5,6)I
WASHINGTON COUNTY

REVISIONS	
NAME	DATE

Rev.

DRAWN BY:

DATE: 02/28/2007 10:00:00 AM
C:\p1\proj\1000000000\1000000000.dwg
REF: REF