

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#	**	ST. CLAIR	34	5
STA. _		TO STA. _		
FED. ROAD DIST. NO. _		ILLINOIS FED. AID PROJECT		
* FAI_64/FAI_255				
** DIST_8_ITS_2008-1_2C				

LEGEND

ALUM	ALUMINUM
EP	EDGE OF PAVEMENT
TW SH	TWISTED SHIELDED
PWR CBL	POWER CABLE
F.O.	FIBER OPTIC
J.B.	JUNCTION BOX
GSC	GALVANIZED STEEL CONDUIT
PVCC	POLYVINYL CHLORIDE CONDUIT
FGC	FIBER GLASS CONDUIT
	EXISTING HANDHOLE
	EXISTING DOUBLE HANDHOLE
	EXISTING CONTROLLER
	EXISTING SERVICE INSTALLATION
	EXISTING GALVANIZED STEEL CONDUIT
	EXISTING JUNCTION BOX
	EXISTING SIGN TRUSS
	EXISTING HIGHWAY LIGHTING UNIT
	EXISTING UNDERGROUND LIGHTING CABLES
	PROPOSED HANDHOLE
	PROPOSED DOUBLE HANDHOLE
	PROPOSED CONTROLLER
	PROPOSED CONDUIT: "T" TRENCH, "P" PUSH "ATS" ATTACHED TO STRUCTURE, SIZE SPECIFIED
	PROPOSED SERVICE INSTALLATION
	PROPOSED CCTV CAMERA
	PROPOSED JUNCTION BOX, SIZE SPECIFIED
	PROPOSED WOOD POLE, SIZE SPECIFIED
	PROPOSED DETECTION SYSTEM (MICROLOOPS)
	PROPOSED LIGHT POLE, SIZE SPECIFIED
	PROPOSED CHANGEABLE MESSAGE SIGN
	PROPOSED VIDEO DETECTION CAMERA
	PROPOSED HIGHWAY ADVISORY RADIO
	PROPOSED RADAR VEHICLE DETECTOR

GENERAL NOTES

- CCTV ARE LOCATION SENSITIVE. PROPOSED EQUIPMENT LOCATIONS ARE APPROXIMATE TO ENSURE THE OPTIMUM FIELD OF VIEW. ACTUAL LOCATIONS SHALL BE DETERMINED IN THE FIELD BY THE CONTRACTOR, PER THE MANUFACTURER REPRESENTATIVES' RECOMMENDATIONS AND THE ENGINEER'S APPROVAL. MR. BRIAN SNEED OF THE BUREAU OF OPERATIONS SHALL BE CONTACTED FOR ACTUAL CAMERA LOCATION VERIFICATION.
 - ALL MATERIALS SUPPLIED SHALL CONFORM TO SECTION 106 OF THE STANDARD SPECIFICATIONS FOR CONTROL OF MATERIALS.
 - THE CONTROLLER CABINETS AND JUNCTION BOXES SHALL BE UNPAINTED ALUMINUM SHEET METAL UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 - UNDERGROUND CABLE MARKING TAPE SHALL BE INSTALLED WITH ALL TRENCH AND BACKFILL FOR ELECTRICAL WORK IN ACCORDANCE WITH ARTICLES 819.05 AND 1066.05 OF THE STANDARD SPECIFICATIONS.
 - A 1/4" DIA. NYLON ROPE SHALL BE INSTALLED IN ALL CONDUIT RUNS. THE COST OF PULL ROPE SHALL BE INCLUDED IN THE PROPOSED ELECTRIC CABLE INSTALLATION AND/OR FIBER OPTIC IN THAT CONDUIT.
 - THE CONTRACTOR SHALL NOT DRILL ANY HOLES IN THE BEAMS, DECK, OR SUBSTRUCTURE OF THE BRIDGE, UNLESS OTHERWISE APPROVED BY THE ENGINEER.
 - ALL GROUND RODS SUPPLIED FOR THIS PROJECT SHALL BE IN ACCORDANCE WITH ARTICLE 1087.01 EXCEPT THAT THEY SHALL BE 3/4" DIAMETER X 12'-0" LONG. ALL CONNECTIONS TO GROUND RODS SHALL BE MADE VIA EXOTHERMIC WELD. COMPRESSION CLAMPS WILL NOT BE ALLOWED.
 - COORDINATION WITH THE DEPARTMENT'S BUREAU OF OPERATIONS IS REQUIRED BEFORE ANY TRENCHING SHALL BE DONE TO LOCATE HIGHWAY LIGHTING/PUMP STATION/ITS FACILITIES AND TO COORDINATE OTHER FIELD ACTIVITIES.
 - BENDING RADIUS OF FIBER OPTIC CABLE SHALL NOT EXCEED SIX (6) INCHES. A MINIMUM OF 20' SLACK CABLE SHALL BE INSTALLED AT EACH CONTROLLER CABINET PRIOR TO TERMINATION OF FIBER.
 - NO OVERNIGHT PERMANENT LANE CLOSURES SHALL BE PERMITTED ON THIS PROJECT.
 - ANY GROUND AREA THAT THE CONTRACTOR COMPACTS OR DISTURBS SHOULD BE SEEDED AT THE END OF EACH WEEK WITH CLASS 7 TEMPORARY EROSION CONTROL SEEDING W/MULCH FOR PERMANENT SEEDING USE CLASS 2A ROADSIDE MIXTURE ALONG THE INTERSTATE.
 - ALL HANDHOLES SHALL BE CONSTRUCTED OF PORTLAND CEMENT CONCRETE (PER ARTICLE 1088.06) THE LEGEND ON THE COVER SHALL BE "ITS". SLOPE HANDHOLE TO MATCH FINAL GRADE ELEVATION. ALL UTILITIES SHALL BE LOCATED IN THE FIELD PRIOR TO ANY ATTEMPT TO CONSTRUCT ANY COMPONENT OF THE VARIOUS CCTV CAMERA SYTEMS AND VIDEO VEHICLE DETECTION SYSTEMS AND INSTALLATIONS.
 - ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AT&T ILLINOIS (COMMUNICATIONS)
 - AMEREN CIPS (ELECTRIC)
 - AMEREN IP (ELECTRIC & GAS)
 - BUCKEYE PIPE LINE COMPANY (PIPELINE)
 - VILLAGE OF CASEYVILLE (SANITARY SEWER)
 - CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - CENTERPOINT ENERGY (PIPELINE)
 - CITY OF COLLINSVILLE (SANITARY SEWER & WATER)
 - ILLINOIS AMERICAN WATER COMPANY (WATER)
 - MCLEOD USA TELECOMMUNICATIONS, INC. (COMMUNICATIONS)
 - MEDIACOM LLC CENTRAL (CABLE TV)
 - MOUND PUBLIC WATER AND SEWER DISTRICT (WATER)
 - QWEST COMMUNICATIONS (COMMUNICATIONS)
 - METRO (COMMUNICATIONS)
- (MEMBER OF J.U.L.I.E. (800-892-0123) ARE INDICATED BY "*". NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)

- A 9-1-1 ADDRESS MUST BE OBTAINED FROM THE ST. CLAIR COUNTY 9-1-1 COORDINATOR PRIOR TO OBTAINING ELECTRIC/ TELEPHONE SERVICE AT THE PROJECT LOCATIONS. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER/TECHNICIAN A MINIMUM OF SIX WEEKS IN ADVANCE OF THE ANTICIPATED DATE THAT ELECTRIC/TELEPHONE SERVICE WILL BE REQUIRED IN ORDER THAT THE NECESSARY ADDRESS CAN BE OBTAINED. IF THERE ARE ANY QUESTIONS REGARDING THE ABOVE, CONTACT THE 9-1-1 COORDINATOR AT 618-277-7316 EXT. 104 FOR ST. CLAIR COUNTY
- THE CONTRACTOR SHALL PAY SPECIAL ATTENTION TO SECTION 107 " LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC " OF THE STANDARD SPECIFICATIONS, IN PARTICULAR, 107.01 "LAWS TO BE OBSERVED AND 107.04 PERMITS AND LICENSES".
- ALL FIBER BACKBONE CONDUIT SHALL BE PLACED A MINIMUM OF 5' FROM EDGE OF PAVEMENT OR AS INDICATED ON THE PLAN SHEETS OR PER FIELD ENGINEER'S RECOMMENDATION.
- FIELD MEASUREMENTS ARE REQUIRED TO VERIFY DIMENSIONS OF EXISTING STRUCTURES PRIOR TO ORDERING MOUNTING HARDWARE.
- FOUNDATIONS: THE CONTRACT UNIT PRICE FOR "CONCRETE FOUNDATIONS" OR "DRILLED SHAFT CONCRETE FOUNDATIONS" SHALL INCLUDE: ALL NECESSARY EXCAVATION OR DRILLING (EXCEPT IN ROCK); BACKFILLING WITH EXCAVATED MATERIAL; DISPOSAL OF SURPLUS MATERIAL; FORMWORK; AND FURNISHING AND PLACING CLASS SI CONCRETE, REINFORCEMENT BARS, CONDUIT, ANCHOR BOLTS, NUTS, WASHERS, AND GROUND RODS COMPLETE IN PLACE.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION GENERAL NOTES, LEGEND, & SPECIFICATIONS FAI 64/FAI 255 SECTION DIST 8 ITS 2008-1, 2C ST. CLAIR COUNTY DATE 5/9/2007
NAME	DATE	

PLOT DATE = 5/9/2007
 FILE NAME = c:\pno\pno\489587\electrod\1\spn\489587a.dgn
 PLOTTER = HP DesignJet 500 / IN.
 REFERENCE = 000000