

**SUMMARY OF QUANTITIES**

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	Y003	
				80% FEDERAL	20 % LOCAL
20100110	TREE REMOVAL (6 TO 15 INCH DIAMETER)	UNIT	100	100	
20100210	TREE REMOVAL (OVER 15 INCH DIAMETER)	UNIT	20	20	
20200100	EARTH EXCAVATION	CUYD	400	400	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5	
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	5	5	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5	
* 25200100	SODDING	SQYD	400	400	
42101300	PROTECTIVE COAT	SQYD	750	750	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	45	45	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	6,100	6,100	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	20	20	
44000300	CURB REMOVAL	FOOT	200	200	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10	
44000600	SIDEWALK REMOVAL	SQFT	14,000	14,000	
60600605	CONCRETE CURB, TYPE B	FOOT	200	200	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	10	10	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
* B2000124	TREE, ACER CAMPESTRE (HEDGE MAPLE), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	16	16	
* B2001124	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 3" CALIPER, TREE FORM BALLED AND BURLAPPED	EACH	16	16	
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	17	17	
* B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	16	16	
* X0324062	ENTRANCE SIGN	L SUM	2	2	
* X0539800	TREE GRATES	EACH	61	61	
X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CUYD	100	100	
XZ191300	AGGREGATE SUBGRADE	CUYD	20	20	
XX003059	DECORATIVE BRICK SIDEWALK	SQFT	11,500	11,500	
* XX005633	ENTRY SIGNAGE	EACH	2	2	
* XX005644	MINOR SIGN COMPLETE	EACH	6	6	
* XX005878	CAST IRON TREE GRATES	EACH	1	1	
* <del>XX007000</del>	PORTLAND CEMENT CONCRETE BASE COURSE, 3"	SQFT	11,500	11,500	
* <del>XX007001</del>	ROOT BARRIER	EACH	63	63	

\* DENOTES SPECIALTY ITEM

Drawing file: W:\Projects\12506335 - Grand Blvd Beautification\SUMMO1.dwg Apr 09, 2007 - 3:00pm



◆ Civil Engineers  
◆ Municipal Consultants  
◆ Established 1911

9933 Roosevelt Road  
Westchester, Illinois 60154-2780  
Phone: 708/865-0300  
Fax: 708/865-1212

**TRANSPORTATION CORRIDOR  
BEAUTIFICATION PROJECT  
VILLAGE OF BROOKFIELD, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE:	NONE	SHEET <b>3</b> OF <b>15</b>
DRAWN BY:	LEV/MK/ECW/TSG	
BOOK NO.:	SDR33	
DATE:	2-9-07	
REVISION:	E.H.E. NO.: 125-06-33580	