

ITEM NUMBER	ITEMS	UNIT	QUANTITY			
			1000	LEMOYNE	34TH	33RD
20200100	EARTH EXCAVATION	CU YD	296	140	134	22
35101400	AGGREGATE BASE COURSE TYPE B	TON	424	200	192	32
40600100	BITUMINOUS MATERIALS(PRIME COAT)	GAL	722	341	326	55
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	271	128	122	21
40600982	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	S.Y.	84	57	13	14
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	82	39	37	6
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	404	191	182	31
44000198	HOT- MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	S.Y.	4725	2218	2156	351
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	655	0	561	94
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	11	0	0
67100100	MOBILIZATION	L SUM	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1			
* 78000400	THERMOPLASTIC PAVEMENT MARKING LINE 6"	FOOT	456	456	0	0
* 78000650	THERMOPLASTIC PAVEMENT MARKING LINE 24"	FOOT	70	42	14	14

* - SPECIALITY ITEM

REVISIONS		
NO.	ITEM	DATE
1	PER IDOT REVIEW	4/2/07

SCALE:	N/A
DRAWN BY:	EB,AG
CHECKED BY:	HMD
DATE:	2-12-07

McClure
Engineering Associates, Inc.
2728 Grand Avenue Waukegan, Illinois 60095-2495
TEL 847-336-7100 FAX 847-336-7155
Design Firm License: Illinois 184-000816
Copyright 2006 by McClure Engineering Associates, Inc.

SUMMARY OF QUANTITIES			
2007 ROADWAY RESURFACING PROJECT			
VILLAGE OF STONE PARK	JOB NUMBER: 02-28-07-005	COOK COUNTY, ILLINOIS	
W:\dwg\SP\2007 RD RESURF\2007RD BASE_recover001.dwg 4/10/2007 8:17:00 AM EDT			