

SUMMARY OF QUANTITIES					
CODE	PAY ITEM	UNIT	TOTAL QTY.	1000-2A 80% Federal 20% Village	1000-2A 100% Village
20800150	TRENCH BACKFILL	CUYD	622	312	310
21101615	TOPSOIL FURNISH AND PLACE, 4"	SOYD	2,175	2,175	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	41	41	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	41	41	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	41	41	0
25200100	SODDING	SOYD	2,175	2,175	0
25200200	SUPPLEMENTAL WATERING	UNIT	25	25	0
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	213	135	78
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,850	1,850	0
40600300	AGGREGATE (PRIME COAT)	TON	28	28	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SOYD	600	600	0
40600310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,814	1,814	0
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SOYD	80	80	0
42101300	PROTECTIVE COAT	SOYD	2,782	2,782	0
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	SOYD	995	995	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQFT	7,490	7,490	0
42400800	DETECTABLE WARNINGS	SOFT	940	940	0
44000100	PAVEMENT REMOVAL	SOYD	80	80	0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SOYD	18,500	18,500	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SOYD	1,015	1,015	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,935	3,935	0
44000600	SIDEWALK REMOVAL	SQFT	7,700	7,700	0
44201329	CLASS C PATCHES, TYPE II, 8"	SOYD	440	440	0
44201333	CLASS C PATCHES, TYPE III, 8"	SOYD	240	240	0
44201335	CLASS C PATCHES, TYPE IV, 8"	SOYD	1,170	1,170	0
* 56400510	FIRE HYDRANTS TO BE REMOVED AND REPLACED	EACH	21	0	21
60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	24	24	0
60228110	MANHOLES, SANITARY, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	0
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	13	13	0
60248700	VALVE VAULTS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6	0
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	20	20	0
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	2	2	0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	44	44	0
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	8	8	0
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	57	57	0
60500040	REMOVING MANHOLES	EACH	2	2	0
60500060	REMOVING INLETS	EACH	16	10	0
60500205	FILLING CATCH BASINS	EACH	31	31	0
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	3,935	3,935	0
67100100	MOBILIZATION	L SUM	1	1	0
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	0
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	595	595	0
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	310	310	0
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	727	727	0
XX003036	STORM SEWERS, PVC, SDR 26, 10"	FOOT	631	631	0
XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	24	24	0
Xx006993	10" X 4" CATCH BASIN TRAP AND RESTRICTOR	EACH	20	20	0
Xx006994	8" X 4" CATCH BASIN TRAP AND RESTRICTOR	EACH	9	9	0
Δ 20076600	TRAINEES	HOURL	500	500	0

\*SPECIALTY ITEMS  
Δ 4080

Drawing File: W:\Projects\56506359 - High Priority Grant\SUM01.dwg Apr 11, 2007 - 2:35pm

 <b>HANCOCK ENGINEERING</b>	◆ Civil Engineers	9933 Roosevelt Road
	◆ Municipal Consultants	Westchester, Illinois 60154-2780
	◆ Established 1911	Phone: 708/865-0300
		Fax: 708/865-1212

**ROADWAY RESURFACING (LAPP)**  
**PROJECT HPP-1717 (001)**  
**VILLAGE OF MAYWOOD, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE:	NONE	SHEET <b>5</b> <b>22</b>
DRAWN BY:	LEV/ECW	
BOOK NO.:	1484/1516/1538	
DATE:	4-12-07	
REVISION:	E.H.E. NO.: 565-06-35901	OF