

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000 - 2A 80% FEDERAL 20% LOCAL
	20200100 Earth Excavation	CuYd	18	18
*	21101610 Topsoil Furnish and Place, 3"	SqYd	310	310
*	25000400 Nitrogen Fertilizer Nutrient	Pound	10	10
*	25000500 Phosphorus Fertilizer Nutrient	Pound	10	10
*	25000600 Potassium Fertilizer Nutrient	Pound	10	10
*	25200100 Sodding	SqYd	310	310
	40300100 Bituminous Materials (Prime Coat)	Gal	600	600
	40600300 Aggregate (Prime Coat)	Ton	12	12
	40600625 Leveling Binder (Machine Method), N50, 3/4"	Ton	225	225
	40600982 Hot-Mix Asphalt Surface Removal - Butt Joint	SqYd	100	100
	40603335 Hot-Mix Asphalt Surface Course, Mix D, N50	Ton	480	480
	40800050 Incidental Hot-Mix Asphalt Surfacing	Ton	32	32
	42000300 Portland Cement Concrete Pavement, 8"	SqYd	55	55
	42400200 Portland Cement Concrete Sidewalk, 5"	SqFt	1700	1700
	42400800 Detectable Warnings	SqFt	220	220
	44000100 Pavement Removal	SqYd	250	250
	44000158 Hot-Mix Asphalt Surface Removal, 2 1/4"	SqYd	5600	5600
	44000600 Sidewalk Removal	SqFt	1700	1700
	44001900 Combination Curb & Gutter Removal (Special)	Foot	365	365
	44002000 Concrete Curb Removal	Foot	50	50
	44201329 Class C Patches, Type II, 8"	SqYd	60	60
	48301000 Protective Coat	SqYd	335	335
	56500600 Domestic Water Service Boxes to be Adjusted	Each	2	2
	60213800 Restricted Depth Catch Basins, 4' Diameter, Type 1 Frame, Open Lid	Each	2	2
	60234200 Inlets, Type A, Type 1 Frame, Open Lid	Each	1	1
	60252800 Catch Basins to be Reconstructed	Each	5	5
	60300305 Frames and Lids to be Adjusted	Each	20	20
	60406000 Frames and Lids, Type 1, Open Lid	Each	1	1
	60406100 Frames and Lids, Type 1, Closed Lid	Each	1	1
	60600605 Concrete Curb, Type B	Foot	50	50
	60604100 Combination Concrete Curb & Gutter, Type B-6.12(Modified)	Foot	365	365
	67100100 Mobilization	LumpSum	1	1
	70101800 Traffic Control & Protection (Special)	LumpSum	1	1
*	78000100 Thermoplastic Pavement Marking - Letters & Symbols	SqFt	10	10
*	78000200 Thermoplastic Pavement Marking - Line, 4"	Foot	275	275
*	78000400 Thermoplastic Pavement Marking - Line, 6"	Foot	270	270
*	78000650 Thermoplastic Pavement Marking - Line, 24"	Foot	110	110

* DENOTES SPECIALITY ITEM

Drawing file: W:\Projects\76007904 - 2007 St Resurf HPP\Summary of quantities.dwg Apr 11, 2007 - 3:33pm



◆ Civil Engineers
◆ Municipal Consultants
◆ Established 1911

9933 Roosevelt Road
Westchester, Illinois 60154-2780
Phone: 708/865-0300
Fax: 708/865-1212

**2007 STREET RESURFACING PROJECT
VILLAGE OF RIVER GROVE, ILLINOIS**

SUMMARY OF QUANTITIES

REVISION:

SCALE: NONE
DRAWN BY: MK
BOOK NO.: 1505
DATE: 04/09/07
E.H.E. NO.: 760-07-00401

SHEET
4
OF
11