

F. A. IL. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1607	07-00114-00-RS 07-00083-00-RS	COOK	016	002
STA.	TO STA.			
FED. ROAD DIST. NO.	SLANDS	FED. AID PROJECT		

CONTRACT #83940

SUMMARY OF QUANTITIES					VILLAGE OF S. HOLLAND	VILLAGE OF DOLTON
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN		
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	6.0	6.0
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	6.0	6.0
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	6.0	6.0
	25200110	SODDING, SALT TOLERANT	SQ YD	600	300.0	300.0
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	100.0	100.0
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4736	2131.0	2605.0
	40600300	AGGREGATE (PRIME COAT)	TON	101	46.0	55.0
	40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1036	466.0	570.0
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3763	1510.0	2253.0
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	100	50.0	50.0
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2450	1225.0	1225.0
	42400800	DETECTABLE WARNINGS	SQ FT	600	300.0	300.0
	44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	8996	4048.0	4948.0
	XX006948	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	100	50.0	50.0
	44000600	SIDEWALK REMOVAL	SQ FT	2450	1225.0	1225.0
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	700	350.0	350.0
	44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	100	50.0	50.0
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	300	150.0	150.0
	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	400	200.0	200.0
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	1550	775.0	775.0
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	40	20.0	20.0
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	1.0	1.0
	60255500	MANHOLES TO BE ADJUSTED	EACH	60	30.0	30.0
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	2.0	2.0
	60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	1.0	1.0
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4000	2000.0	2000.0
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	300	150.0	150.0
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16800	8400.0	8400.0
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2400	1200.0	1200.0
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2000	1000.0	1000.0
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450	225.0	225.0
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1142	571.0	571.0
	X0324096	HOT IN-PLACE RECYCLING	SQ YD	43760	19692.0	24068.0
	X0322052	ASPHALT REJUVENATING AGENT	GALLON	4376	1969.0	2407.0
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1240	558.0	6820
	67100100	MOBILIZATION	L SUM	1	0.5	0.5

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF BITUMINOUS MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS SURFACE IS PLACED.

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

154TH STREET
STREET RESURFACING
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE 04-16-07

DRAWN BY PS/RG
CHECKED BY PKB

ROBINSON ENGINEERING, LTD.
17000 SOUTH PARK AVENUE, SOUTH HOLLAND, ILLINOIS 60470
(708) 891-8700 FAX (708) 381-9620
ILLINOIS DESIGN FIRM REGISTRATION NO. 150001128 06187-QUAN-01