

ITEM #	ITEM	UNIT	QUANTITY	PARTICIPATING	NON-PARTICIPATING
XX003461	Earth Excavation, Special	L SUM	1	1	
20700220	Porous Granular Embankment	CU YD	5	5	
20800150	Trench Backfill	CU YD	25	25	
25000900	Seeding, Class 1 (Special)	ACRE	0.2	0.2	
28000510	Inlet Filters	EACH	2	2	
35100100	Aggregate Base Course, Type A	TON	62	62	
42001000	High-Early-Strength Portland Cement Concrete Pavement 9"	SQ YD	219	219	
42001200	Pavement Fabric	SQ YD	219	219	
42001300	Protective Coat	SQ YD	375	375	
42400100	Portland Cement Concrete Sidewalk 4 Inch	SQ FT	825	825	
42400800	Detectable Warnings	SQ FT	36	36	
44000200	Driveway Pavement Removal	SQ YD	90	90	
44000500	Combination Curb and Gutter Removal	FOOT	185	185	
44000600	Sidewalk Removal	SQ FT	370	370	
44002020	Concrete Median Surface Removal	SQ FT	193	193	
44002212	Hot-Mix Surface Removal Over Patches, 3"	SQ YD	112	112	
50300225	Concrete Structures	CU YD	20	20	
50300254	Rubbed Finish	SQ FT	42	42	
50800105	Reinforcement Bars	POUND	2377	2377	
55100500	Storm Sewer Removal 12"	FOOT	41	41	
60235700	Inlets, Type A, Type 3 Frame and Grate	EACH	1	1	
60255500	Manholes to be Adjusted	EACH	4	4	
60260300	Inlets to be Adjusted with New Type 1 Frame, Open Lid	EACH	1	1	
60260500	Inlets to be Adjusted with New Type 3 Frame and Grate	EACH	1	1	
60266600	Valve Boxes to be Adjusted	EACH	2	2	
60605000	Combination Concrete Curb and Gutter, Type B-6.24	FOOT	120	120	
60618300	Concrete Median Surface, 4 Inch	SQ FT	193	193	
67100100	Mobilization	L SUM	1	1	
70102620	Traffic Control and Protection, Standard 701501	L SUM	1	1	
70102625	Traffic Control and Protection, Standard 701606	L SUM	1	1	
70102635	Traffic Control and Protection, Standard 701701	L SUM	1	1	
70102640	Traffic Control and Protection, Standard 701801	L SUM	1	1	
70103700	Traffic Control Complete	L SUM	1	1	
* 78005100	Epoxy Pavement Marking - Letters and Symbols	SQ FT	32	32	
* 78005130	Epoxy Pavement Marking - Line 6"	FOOT	252	252	
* 78005180	Epoxy Pavement Marking - Line 24"	FOOT	10	10	
* 78300105	Pavement Marking Removal	FOOT	171	171	
* 81012600	Conduit in Trench, 2" Dia., PVC	FOOT	171	171	
* 81013000	Conduit in Trench, 4" Dia., PVC	FOOT	29	29	
* 81021330	Conduit Pushed, 2" Dia., PVC	FOOT	10	10	
* 81021370	Conduit Pushed, 4" Dia., PVC	FOOT	100	100	

H28 07C

ITEM #	ITEM	UNIT	QUANTITY	PARTICIPATING	NON-PARTICIPATING
* 81400100	Handhole	EACH	3	3	
* 81400730	Handhole, Composite Concrete	EACH	1	1	
* 81603045	Unit Duct, 600V, 3-1C No. 6 1/C No. 6 Ground, (XLP-Type Use), 1" Dia. Polyethylene	FOOT	205	205	
* 81900200	Trench and Backfill for Electrical Work	FOOT	200	200	
* 87301245	Electric Cable in Conduit, Signal No. 14 5C	FOOT	90	90	
* 87301255	Electric Cable in Conduit, Signal No. 14 7C	FOOT	310	310	
* 87301305	Electric Cable in Conduit Lead-in, No. 14 1 Pair	FOOT	240	240	
* 87502700	Traffic Signal Post, Aluminum 16 FT.	EACH	2	2	
* 87600100	Pedestrian Push-Button Post, Type 1	EACH	1	1	
* 87800100	Concrete Foundation, Type A	FOOT	3	3	
* 87900100	Drill Existing Foundation	EACH	1	1	
* 87900200	Drill Existing Handhole	EACH	1	1	
* 88040150	Signal Head, Polycarbonate, LED, 1-Face, 5-Section, Bracket Mounted	EACH	2	2	
* 88200410	Traffic Signal Backplate, Louvered, Formed Plastic	EACH	2	2	
* 88500100	Inductive Loop Detector	EACH	1	1	
* 88600100	Detector Loop, Type 1	FOOT	204	204	
* 89500100	Relocate Existing Signal Head	EACH	2	2	
* 89500200	Relocate Existing Pedestrian Signal Head	EACH	2	2	
* 89500400	Relocate Existing Pedestrian Push-Button	EACH	2	2	
* 89502100	Rebuild Existing Signal Head	EACH	2	2	
* 89502110	Rebuild Existing Pedestrian Signal Head, LED	EACH	2	2	
* 89502200	Modify Existing Controller	EACH	1	1	
* 89502210	Modify Existing Controller Cabinet	EACH	1	1	
* 89502375	Remove Existing Traffic Signal Equipment	EACH	1	1	
* 89502380	Remove Existing Handhole	EACH	1	1	
550A0050	Storm Sewers, Class A, Type 1, 12"	FOOT	40	40	
X0323426	Sediment Control, Drainage Structure Inlet Filter Cleaning	EACH	2	2	
* XX003163	Emergency Vehicle Priority System	EACH	1		1
XX006067	Pipe Underdrains, Perforated PVC, 6 Inch	FOOT	60	60	
XZ188000	Retaining Wall Removal	L SUM	1	1	
Z0017100	Dowel Bars	EACH	125	125	
XX006990	Remove and Replace Existing Gutter, Gutter Outlet & Inlet (Special) with Type 1 Frame, Open Lid	L SUM	1	1	
XX006991	Brick Facade	SQ FT	200	200	
XX006992	Dowel Bars, Special	EACH	12	12	

* SPECIALTY ITEMS

	MILANO & GRUNLOH ENGINEERS, LLC	SUMMARY OF QUANTITIES
	14 WEST WASHINGTON P.O. BOX 897 EFFINGHAM, ILLINOIS 62401	BANKER STREET
	PHONE: (217) 547-7282 (800) 577-2714	CITY OF EFFINGHAM
	FAX #: (217) 542-3433	
File name: S:\DWG\03\03003RTL\dwg\Quantities.dwg Plot date: 05/24/07 at 09:10		