

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9104 05-00001-00-WR	MADISON	102	3	
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		
CONTRACT NO. 97914				

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	6985
20800150	TRENCH BACKFILL	CU YD	440
25000100	SEEDING, CLASS 1	ACRE	3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	290
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	290
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	290
25100115	MULCH, METHOD 2	ACRE	3
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300
28000300	TEMPORARY DITCH CHECKS	EACH	38
28000400	PERIMETER EROSION BARRIER	FOOT	736
28000500	INLET AND PIPE PROTECTION	EACH	10
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	310
28200200	FILTER FABRIC	SQ YD	310
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	14319
30201700	PORTLAND CEMENT	TON	644
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	13503
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	310
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	478
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	126
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	12012
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250
42001200	PAVEMENT FABRIC	SQ YD	12012
42001300	PROTECTIVE COAT	SQ YD	12868
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	105
44000100	PAVEMENT REMOVAL	SQ YD	7849
44000300	CURB REMOVAL	FOOT	293
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1241
44002805	ISLAND REMOVAL	SQ FT	385
44003100	MEDIAN REMOVAL	SQ FT	940
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1430
50105220	PIPE CULVERT REMOVAL	FOOT	515


* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
54207153	PIPE CULVERTS, TYPE I, REINFORCED CONCRETE ELLIPTICAL, EQUIVALENT ROUND - SIZE 18"	FOOT	214
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION, 15"	EACH	1
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTION, 48"	EACH	1
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTION, 60"	EACH	1
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTION - ELLIPTICAL, EQUIVALENT ROUND - SIZE 18"	EACH	8
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	118
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	63
55020500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 48"	FOOT	64
55020700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS I 60"	FOOT	72
60242900	INLETS, SPECIAL, TYPE 1	EACH	2
60243000	INLETS, SPECIAL, TYPE 2	EACH	2
60243100	INLETS, SPECIAL, TYPE 3	EACH	2
60500060	REMOVING INLETS	EACH	4
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	719
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	750
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3067
63200310	GUARDRAIL REMOVAL	FOOT	141
66410300	CHAIN LINK FENCE REMOVAL	FOOT	545
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	284
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	371
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12697
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	464

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	761
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	159
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3917
* 72000100	SIGN PANEL - TYPE 1	SQ FT	66
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	29
72900200	METAL POSTS - TYPE B	FOOT	122
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	3
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1586
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	183
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	33
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	371
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	102
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	159
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	11111
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	281
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	626
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	118
* 78200300	PRISMATIC CURB REFLECTOR	EACH	26
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	100
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1006
* 88600100	DETECTOR LOOP, TYPE I	FOOT	542
* 89502100	REBUILD EXISTING SIGNAL HEAD	EACH	3
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	703
XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	215
* X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	69
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	749



SUMMARY OF QUANTITIES

**BISSELL STREET
MADISON, ILLINOIS
SECTION No. 05-00061-00-WR**

REVISIONS			
NO.	DATE	BY	REMARKS

SCALE: NOT TO SCALE			
DSN. BY: BFK	DATE: 1/19/07	SHEET	3
DWN. BY: JDH	DATE: 1/19/07		
CHK'D: BFK	DATE: 1/19/07		
JOB NO. E061300		DGN. NAME: SUMQTY OF 102 SHTS	

BY	DATE	FINAL SURVEY PLOTTED	NO.

BY	DATE	ORIGINAL SURVEY PLOTTED	NO.