

CURB AND GUTTER REMOVAL AND REPLACEMENT SCHEDULE

STATION	LIN. FT.	STATION	LIN. FT.
0+79 RT TO 0+95 RT	16	4+27 RT TO 4+45 RT	19
1+24 LT TO 1+39 LT	26	4+80 LT TO 4+92 LT	24
1+25 RT TO 1+28 RT	8	4+80 RT TO 5+20 RT	40
2+19 RT TO 2+76 RT	67	5+74 RT TO 5+95 RT	21
2+75 LT	10	6+30 RT TO 6+40 RT	10
2+94 RT TO 3+03 RT	12	6+60 LT TO 6+75 LT	15
3+10 RT TO 3+15 RT	5	7+08 RT TO 7+18 RT	10
3+34 RT TO 3+49 RT	15	7+16 LT TO 7+54 LT	38
3+77 RT TO 3+85 RT	8	7+67 LT TO 8+33 LT	66
4+13 LT TO 4+35 LT	22	8+31 RT TO 8+38 RT	7

TOTAL 439

SIGNING SCHEDULE

APPROXIMATE LOCATION	TYPE	NO.	SIGN (SQ.FT.)	POSTS (EACH)
1+85 RT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
2+20 LT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
3+40 RT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
3+90 LT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
6+00 RT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
6+50 LT	NO PARKING 2AM-4AM	R7--(12X18)	1.50	1
6+75 LT	EXISTING POST OFFICE SIGN		-	1
7+05 LT	EXISTING POST OFFICE SIGN		-	1
7+30 LT	EXISTING POST OFFICE SIGN		-	1
7+40 LT	EXISTING POST OFFICE SIGN		-	1
7+74 LT	EXISTING POST OFFICE SIGN		-	1
7+92 LT	EXISTING POST OFFICE SIGN		-	1

TOTALS 9.00 12

SUMMARY OF QUANTITIES

ITEM NO.	PAY ITEM	UNIT	QUANTITY
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	370
42400500	PORTLAND CEMENT CONCRETE SIDEWALK SPECIAL	SQ. FT.	15,890
42400800	DETECTABLE WARNINGS	SQ. FT.	114
44000600	SIDEWALK REMOVAL	SQ. FT.	16,260
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	439
67100100	MOBILIZATION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ. FT.	9.0
△ A2008016	TREE, TILIA CORDATA (LITTLE LEAF LINDEN) 2' CALIPER, BALLED AND BURLAPPED	EACH	8
△ X0300635	PLANTER	EACH	8
△ X0444100	BENCHES	EACH	8
△ XX002918	TREE FRAME AND GRATES	EACH	8
△ Z0020000	ELECTRICAL SYSTEM COMPLETE	L SUM	1
△ Z0042500	POST, SPECIAL	EACH	12

△ SPECIALTY ITEMS

TREE, FRAME AND GRADE LOCATIONS

STATION	OFFSET
1+99	31' RT
2+38	31' LT
3+68	31' RT
3+86	31' LT
5+30	31' RT
5+88	31' LT
7+26	31' LT
7+85	31' RT

SIDEWALK REMOVAL AND REPLACEMENT SCHEDULE


STATION	SIDEWALK REMOVAL SQ. FT.	PC SIDEWALK SQ. FT.	PC SW SPECIAL SQ. FT.	DETECTABLE WARNINGS SQ. FT.
1+24 LT to 2+75 LT	2185	-	2185	12
2+94 LT to 4+47 LT	1835	-	1835	18
4+80 LT to 8+44 LT	4150	-	4150	24
0+80 RT to 1+01 RT	240	240	-	6
1+25 RT to 2+75 RT	1815	-	1815	12
2+95 RT to 4+46 RT	1960	130	1830	18
4+80 RT to 8+43 RT	4075	-	4075	24

TOTALS 16,260 370 15,890 114

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00054-00-SW	FRANKLIN	9	2
WEST FRANKFORT		MAIN STREET		

CONTRACT NO. 99302
PROJECT NO. TE-00D9(93)

BROWN AND ROBERTS, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
1 WEST RIDGE ROAD HARRISBURG, IL. 62946 (618) 252-8111



CITY OF WEST FRANKFORT
STREETSCAPE IMPROVEMENTS
SUMMARY OF QUANTITIES

Drawn By: ECB
Checked By: MWR

Revisions
Item Date By

Scale: AS SHOWN
Field Bk:

Job Number: 05-136
Date: 03/2007

Sheet

31 May 2007 - 9:50am X:\2005\05136\ac\plans\quantity and detail sheets.dwg: Layout Tab Model